

RC 1324

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI27042PA346

For corners in

Wayne
County:
SUMPTER TOWNSHIP

Located in: Corner Code #

1. Public Land Survey	T 4 S	R 8 E	C-11
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-15-93 *DBJ*

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1324

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kenneth S. Wilkerson in a field survey on October 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11 Set Post - GLO - NO GLO WITNESSES REMAIN
Fd. Stone - B of T
Fd. Stone - WCRC 9/05/90
Fd. Stone - L. 19684, P. 39 - 2/22/77

SE 38.30 nail N face 16" cherry
S 33.88 nail E face 18" maple
NW 28.32 nail SW face 4" cherry
NW 25.98 nail E face 8" cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

C-11 Fd stone
Verified by description and previous witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 1/2" x 18" iron rod in stone with Wayne County remonumentation washer and OHM - KSW 21584 cap

C-11 167 az 59.56 NW cor barn
252 az 101.06 top nut on hyd.
287 az 65.21 OHM tag in SW face 14" maple
309 az 35.95 OHM tag in SW face 11" maple


The selected location is accepted as a careful and faithful perpetuation of the position of the original government corner.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

93 DEC 15 PM 4:59
FOREST S. YOUNGBLOOD
REGISTER OF DEEDS
WAYNE COUNTY, MI

Signed by: *[Signature]*

Date: _____



Drafted By: Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.
34935 Schoolcraft Road * Livonia, Michigan 48150 * Phone: (313) 522-6711

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

*2R
11K1*