

FEB 28 1994

COMMISSION

RC 1328

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127042PA350

For corners in

Wayne
County:
SUMPTER TOWNSHIP

Located in: Corner Code #

1. Public Land Survey		T 4 S	R 8 E	G-07
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-15-93
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1328

I, Kenneth S. Wilkerson in a field survey on October 04, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-07 Set Post - GLO - NO GLO WITNESSES REMAIN
Fd. Iron - B of T
Fd. Iron - WCRC - 4/13/72
Fd 1/2" red in mon box, L. 19024, P. 278 - 1/03/74

N 40 E 47.20 nail & cap in P & MBT P
S 65 E 66.38 nail & cap in 30" oak
S 45 W 38.38 nail & cap in MBT P
N 20 W 61.08 nail & cap in MBT P

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-07 Fd 5/8" pipe in mon box

Verified by witnesses and observation per L. 19024, P. 278

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Wayne County remonumentation washer and OHM - KSW 21584 cap on iron.

G-07 053 az 46.92 WCRC tag SE face UP
120 az 66.27 OHM tag NE face 33" oak
225 az 38.27 WCRC tag SE face UP
330 az 60.17 top nut on hyd

The selected location is accepted as the best evidence of the position of the original corner.

Signed By:

Date:



Drafted By: Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.
34935 Schoolcraft Road * Livonia, Michigan 48150 * Phone: (313) 522-6711

FOR STATE APPROVAL BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

FORESTER YOUNGBLOOD
REGISTER OF DEEDS
WAYNE COUNTY, MI

93 DEC 15 PM 4: 59

22
11KD