

**SURVEY & MONUMENTATION CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

APR 05 1996

G-08 Page 1

For corners in Wayne County, Michigan in: **COMMISSION** Sumpter Corner Code

- 1. Public Land Survey T 4 S R 8 E G-08  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 11-30-95 [Signature]  
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp and File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth S. Wilkerson in a field survey on 06/06/1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:  
01/01/1819 Wampler G.L.O. Set post  
15" ELM N 29 E 27 LINKS (17.82') (GONE)  
12" ELM S 33 W 20 LINKS (13.20') (GONE)

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Fd. 1/2" rod in mon. box (no lid) @ int. of cl's of Sumpter & Wear Rds. Dist to G-7 = 2649.75' (R), 2649.59' (M), & Dist. to G-9 = 2644.22' (R) 2644.45' (M) & Angle = 180-59-00 (R) 180-59-00 (M)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
06/06/1995 Wilkerson 21584 O.H.M. Remon.  
SET W.C.R. WASHER & CAP OVER FD. CORNER. REPLACED LID.  
3 W.C.R. TAG W./S P.P. S 37 E 46.10'  
6 W.C.R. TAG S.W./S P.P. N 38 W 47.55'  
8 W.C.R. TAG W. SIDE 16" OAK S 19 E 71.65'  
11 TOP BOLT ON HYDRANT S 37 W 59.70'  
12 W.C.R. TAG N.W. SIDE 20" ASH N 65 E 98.80'

\$ 10.00 DEED  
21 DEC 95 9:17 A.M. RECEIPT# 5B  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
\$ 4.00 REMONUMENTATION

95273112

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date \_\_\_\_\_  
Drafted by Kenneth S. Wilkerson  
Surveyor's Michigan License No. 21584



Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

42  
10/2/95

## A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1930

Wayne Co.  
Bureau of  
Taxation

Set iron

LIBER 28477 PAGE 193

- 1 M.B.T. POLE N.W. 43.00' (GONE)
- 2 CROSS IN NE COR. SIGN POST S.W. 45.00' (GONE)
- 3 ED. POLE S.E. 46.23' (GONE)
- 4 24" ELM S.E. 34.30' (GONE)
- 5 12" ELM N.E. 140.75' (GONE)
- 13 DIST = 2644.22' (R) TO G-09 & 2644.45' (M 1995)
- 14 DIST = 2649.75' (R) TO G-07 & 2649.59' (M 1995)
- 15 ANGLE = 180-59-00 (R) & 180-59-00 (M 1995)

04/13/1972

Klopshinske

W.C.R.C.

Mon. in box

- 6 ED. POLE N.W. 47.75'
- 7 IRON S.W. 47.49
- 8 12" OAK S.E. 71.80'

03/12/1975

Crossman

9428

R.C.3

Fd. mon in road box

- 6 W.C.R.C. CAP IN P.P. N 45 W 47.75'
- 9 W.C.R.C. SIGN S 45 W 47.55'
- 10 D.E. POLE S 60 W 46.15'

05/03/1979

Sandomierski

24616

R.C.6

Fd. mon. in box

- 3 P.K. NAIL SW SIDE P.P. S 30 E 46.50'
- 6 REF. NAIL SW SIDE D.E. GUY POLE N 45 W 47.47'
- 9 CENTERLINE STREET SIGN S 40 W 45.53'
- 11 CENTERLINE TOP BOLT HYD. S 30 W 59.73'

FILED DO NOT MAIL