

LAND CORNER RECORDATION CERTIFICATE

APR 05 1996 Filing Requirement of Act 74, Mich. P.A. 1970

H-05 Page 1

For corners in Wayne County

COMMISSION Located In: Sumpter Corner Code H-05

1. Public Land Survey	T	4	S	R	8	E	
	T			R			
	T			R			
	T			R			
2. Property Controlling In Section	S			T			
	S			T			
3. Miscellaneous Property in Sec.	S			T			
	S			T			
4. Lot No. _____, Recorded Plat _____							
5. Private Claims _____							

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-30-95 *W.P.L.*

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp and File Number

I, Kenneth S. Wilkerson In a field survey on 06/06/1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restorations:
 01/01/1819 Wampler G.L.O. Set post
 ONLY ONE WITNESS
 8" ASH N 67 E 18 LINKS (11.88') (GONE)

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Fd. 3/4" pipe in mon. box w/W.C.M.B. cover in asph. pvm't. @ cl of Judd Rd. DIST TO G-5 2904.09(R) 2899.40 (M) DIST TO I-5 2824.65'(R) 2829.78 (M)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 06/06/1995 Wilkerson 35994 O.H.M. Remon.

- SET W.C.R. WASHER & CAP ON CORNER.
- 5 W.C.R. TAG W/PK NAIL E/S P.P. S 20 E 59.52'
- 7 W.C.R. TAG W/S P.P. N 5 W 31.13'
- 9 S.E. COR. HSE.#44450 N 20 W 157.58
- 11 W.C.R. TAG W/PK. NAIL E/S GUARD RAIL POST S 75 W 159.28

\$ 10.00 DEED
 21 DEC 95 9:18 A.M. RECEIPT# 5B
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION

95273114

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature]
 Drafted by Kenneth S. Wilkerson
 Surveyor's Michigan License No. 21584
 Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

Date Dec 8 1995



*4 P
10 P.S*

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1930

Wayne Co.
Bureau of
Taxation

Iron

LIBER 28477 PAGE 197

- 1 6" & 8" ELM S.E. 27.48' (GONE)
- 2 10" TWIN MAPLE N.E. 37.50'
- 3 40" POPLAR N.W. 62.92' (GONE)
- 4 TREE N.W. 31.00' (GONE)
- 12 DIST = 2904.09' TO G-05
- 13 DIST = 2824.65' TO I-05

03/12/1972

Reynolds

W.C.R.C.

Iron

- 2 SPIKE IN TOP 30" STUMP N.E. 37.94' (GONE)
- 5 DE POLE SPIKE IN SW SIDE S.E. 59.73'
- 6 CUT "+" NE RIM WATER MH S.W. 35.14' (DIDN'T FIND)
- 7 SPIKE IN M.B.T. POLE N.W. 30.37'

07/31/1979

Roskelly

18663

Roskelly &
Jekabson

Fd. 3/4" pipe

- 5 NAIL IN DE POLE S 23 E 59.75'
- 7 NAIL IN M.B.T. POLE N 5 W 30.95'
- 8 NAIL IN M.B.T. POLE N 75 E 169.45' (GONE)
- 9 SE COR. HOUSE N 20 W 157.55'

04/14/1986

Raines

14981

R.C.8

Fd. mon. in handhole

- 5 P.K. NAIL N SIDE DE POLE S 18 E 59.55'
- 7 P.K. NAIL S SIDE M.B.T. POLE NORTH 30.80'
- 10 P.K. NAIL IN E SIDE OF GUARD RAIL POST N 60 W 128.
- 11 P.K. NAIL IN N SIDE OF GUARD RAIL POST S 75 W 159.

FILED DO NOT MAIL