

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

I-09 Page 1

L129366PA885

For corners in

Wayne

Located in: Sumpter Corner Code

County

1. Public Land Survey		T 4 S R 8 E	I-09
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S	T _____ R _____	_____
	S	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S	T _____ R _____	_____
	S	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-16-96 *DBJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp and File Number

I, Kenneth S. Wilkerson in a field survey on 02/01/1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restorations:

01/01/1816 Wampler G.L.O. Set post
REMAIN AT THIS CORNER
NO WITNESSES

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3/4" iron pipe in mon box, at Martinsville & Willow, no lid, dist to J-09 = 2647.52'(R) 2647.95'(M) and to I-10 = 2645.85'(R) 2645.98'(M) (ASPHALT RD.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

02/01/1996 Wilkerson 21584 O.H.M. Remon

- SET W.C.R. WASHER AND CAP OVER FD. 3/4" IRON PIPE.
- 5 S 10 E SET WCR TAG IN 20" SYC. TREE 114.68'
- 6 S 30 W SET TAG E SIDE LIGHT POLE 77.25'
- 9 N 30 W SET WCR TAG IN S SIDE DE POLE 45.40'
- 10 N 60 W TOP OF HYD. 70.81'

\$ 10.00 DEED
30 DEC 96 1:37 P.M. RECEIPT# 44B
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
\$ 4.00 REMONUMENTATION

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by *Kenneth S. Wilkerson* Date Dec 26, 1996
Drafted by Kenneth S. Wilkerson
Surveyor's Michigan License No. 21584

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150



4
10
DB

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1930

W.C. B/T

Iron

- 1 CROSS ON W.C.R. SIGN POST NE 35.68' (gone)
- 2 ED. POLE SE 47.64' (gone)
- 3 FENCE POST SW 48.65' (gone)
- 4 8" MAPLE NW 16.60' (gone)

LI29366PA886

06/01/1970

W.C.R.C.

Iron w/ mon

- 5 12" SYCAMORE SE 114.12' (R) 114.68' (M)
- 6 M.B.T. POLE SW 77.35'(R) 77.25' (M)
- 7 M.B.T. POLE NW 41.94' (gone)
- 8 12" CHERRY NW 46.54' (gone)

06/16/1970

Johns

W.C.R.C.

Iron in mon box

SAME AS ABOVE