

APR 05 1998 Filing Requirement of Act 74, Mich. P.A. 1970

I-12 Page 1

For corners in Wayne County
COMMISSION Located in: Sumpter Corner Code

- 1. Public Land Survey T 4-S R 8-E I-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-30-95
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp and File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth S. Wilkerson in a field survey on 06/23/1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

- 12/03/1993 Platz 38121 1374 Fd. 1/2" iron rod
- 3 CENTERLINE TOP HYD. N55E 43.28'
- 6 P.K. NAIL & TAG S.W. FACE 8" POPLAR N28W 82.62'


(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" I. rod in center of Martinsville Rd. 6" deep in gravel, dist to I-13 = 2661.47 (r), 2662.23 (m), to I-11 = 2660.46' (R) 2660.72 (M)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 06/23/1995 Wilkerson 21584 O.H.M. Remon.
- SET W.C.R. CAP OVER FD. 1/2" IRON
- 3 N55E 43.30' TO TOP BOLT ON HYD.
- 5 S30W 46.30' TP P.K. NAIL & TAG IN E/S OF 11" TWIN OAK
- 6 N28W 82.43' TO SET W.C.R. TAG IN SW/S OF 10" POPLAR.
- 10 S79E 33.04' TO P.K. NAIL & TAG IN S/S OF U.P.



\$ 10.00 DEED
21 DEC 95 9:19 A.M. RECEIPT# 5B
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
\$ 4.00 REMONUMENTATION

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date Dec 8 1995
Drafted by Kenneth S. Wilkerson

Surveyor's Michigan License No. 21584
Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

95273116

AR
10/25

A. (Continued) Description of original monument and accessories and/or subsequent restorations:

01/01/1819

G.L.O. SET POST

ON THIS CORNER
NO WITNESSES

01/01/1930

WAYNE CO.
B/TAXATION

IRON

- 1 NAIL N. SIDE OF 4" CHERRY SW. 84.25'
- 2 NAIL SW. SIDE OF ED. POLE SE. 157.48'
- 7 DIST TO I-11 2660.46 (R) ,2660.72' (M 1995)
- 8 DIST. TO I-13 = 2661.47' (R) 2662.23' (M 1995)
- 9 BS I-13 FS I-11, ANGLE TO R. = 179-53-10 (R) 179-54-10 (M 1995)

12/03/1993

Platz

38121

1374

Fd. 1/2" iron rod

- 4 P.K. NAIL & TAG S/S U.P. S69E 33.03'
- 5 P.K. NAIL & TAG E. FACE 12"OAK S59W 46.25'