

RC 1331

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LI 27042 PA 353

For corners in

Wayne  
County:  
SUMPTER TOWNSHIP

Located in: Corner Code #

1. Public Land Survey	T 4 S	R 8 E	K-03
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-15-93 [Signature]

WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1331

I, Kenneth S. Wilkerson, in a field survey on October 04, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-03 Set Post - GLO - NO GLO WITNESSES REMAIN  
Fd. Mon. - B of T  
Fd. Iron - 6/17/70  
Fd T iron, L. 18598, P. 620 - 2/02/73

N 42 E 45.85 PK in W face fence post  
S 87 E 30.44 PK & cap in N face MBT P  
S 88 E 42.63 PK & cap in N face 14" maple  
S 50 W 43.86 PK & cap in SE face 27" oak  
W 30.29 PK in S face of fence post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-03 Fd T iron 3" below gravel  
Verified from corner certificate per L. 18598, P. 620

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Wayne County remonumentation washer and OHM - KSW 21584 cap on iron.  
K-03 085 az 31.39 PK in S face fence post  
220 az 44.18 OHM tag NW face 20" oak  
268 az 40.34 PK in N face 13" oak  
280 az 29.94 PK in S face fence post

The selected location is accepted as the best evidence of the position of the original corner.

Signed by: [Signature]



Date: 12-15-93

Drafted By: Kenneth S. Wilkerson  
Surveyor's Michigan License No. 21584

Orchard, Hiltz & McCliment, Inc.  
34935 Schoolcraft Road \* Livonia, Michigan 48150 \* Phone: (313) 522-6711

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

93 DEC 15 PM 4:59  
FOREST E. YOUNGLOD  
REGISTERED DEEDS  
WAYNE COUNTY MI

22  
11K7