

**SURVEY & REMONUMENTATION**

DEC 02 1993

**RC 1117**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**LI 26951 PA 748**

For corners in

Wayne <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
**ACT 345, P.A. 1990**  
**APPROVED ON: 10-28-93 PJ**  
**WAYNE COUNTY REMONUMENTATION**  
**PEER GROUP COMMITTEE**

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bruce Antcliff, in a field survey on August 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post  
 WPA (1930's) - Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" I.D. Pipe-evidence of old fence running west and south. Distance to NE Cor. S.31 checks ± 1' with WPA Survey. Distance also checks ± 0.2' w/proposed site condo by Boyd Arthurs.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 36" Con. Monument w/Wayne County Remonumentation Marker and Cap #25826

Witnesses

- P.K. N. Side 12" Walnut, West, 38.70'
- P.K. E. Side 15" Oak, South, 13.44'
- Nail and Tag N. Side 10" Poplar, East 5.63'
- P.K. SW Side 10" Oak, SE, 33.96'
- P.K. S. Side 8" Sassaphrass, NE, 38.85'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff  
 Surveyor's Michigan License No. 25826

Date 11-10-93



25  
 119