

SURVEY & REMONUMENTATION

RC 1119

DEC 02 1993

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LI 26951 PA 750

COMMISSION
 For corners in

<u>Wayne</u> (County)	Located in:	Corner Code -#
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 10-28-93 *DJ*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1119

I, Bruce Antcliff, in a field survey on August 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-Post
- WPA (1930's) - Iron
- MDOT (1965)-Iron Pipe
- MDOT (1977)-Mon. in Mon. box
- LCRC (1987)-Mon. in Mon. box (L23239, P 951)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Mon. in Mon. Box Near W. End Bridge Over I-275.
 Distance to E. 1/4 S.20 checks well with WPA Survey and ALTA Survey by Atwell-Hicks. Distance to N. 1/4 S.20 checks well with Atwell-Hicks but is 1.6' ± longer than WPA Survey

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Wayne County Remonumentation Marker and Cap 25826 on exist. monument

Witnesses

- P.K. Top of Rail Post, NW, 58.08'
- P.K. Top of Rail Post, SW, 85.77'
- S.W. Bolt, W. End 4" Alum. Guard Rail, NE, 45.04'
- "X" near W. End Conc. Bridge Rail, SSE, 56.36'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff
 Surveyor's Michigan License No. 25826

Date 11-10-93



25826

93 NOV 10 PM 2:27
 FOREST COUNTY REGISTER OF DEEDS
 GRAND RAPIDS, MI