

**SURVEY &
REMONUMENTATION**

RC 1120

DEC 02 1993

LI 26951 PA 751

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

Wayne (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 10-28-93 1100
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1120

I, Bruce Antcliff, in a field survey on August 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post
WPA (1930's) - Iron
LCRC (1973)-Iron in Handhole (L18340, P 692)
Rec. Survey (1981)-Iron w/Cap (L18960, P 691)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/8" Capped Iron in Mon. Box; Measured to S 1/4 S.4-Checks well w/WPA Survey; Measured to SE S.3-Checks well w/WPA Survey and Edison Survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 36" Conc. monument w/Wayne County Remonumentation Marker and Cap #25826

Witnesses

*+ on S. Rim Gatewell, N65W, 72.11'
Nail & WCRC Tag S. Side MBT Pole, S60W, 79.90'
Nail & WCRC Tag NE Side MBT Pole, S45E, 46.40'
Top Center Fire Hyd., N30E, 71.92'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Signed by Bruce Antcliff 25826

Date 11-10-93

Surveyor's Michigan License No. _____

26951