

**SURVEY & REMONUMENTATION**

**RC 1122**

DEC 02 1993

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**LI 26951 PA 753**

For corners in  
**COMMISSION**  
 Wayne  
(County)

Located In: Corner Code #

|                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>4S</u> R <u>9E</u> | <u>G-11</u> |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

Compliance with  
**ACT 345, P.A. 1990**

APPROVED ON: 10-28-93 *NCO*  
**WAYNE COUNTY REMONUMENTATION**  
**PEER GROUP COMMITTEE**

Register of Deeds Stamp & File Number

**RC 1122**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Bruce Antcliff, in a field survey on August 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-Post
- WPA (1930's)- Stone
- Rec. Survey (1977)-Drill Hole in Conc. (L19952, P 439)
- LCRC (1978)-Iron (L20031, P 189)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd. 5/8" Iron; Measured to E 1/4 S.28 and S 1/14 S. 28-  
 Match well with w/WPA Surveys and Rec. Surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" X 36" Conc. Monument w/Wayne County Remonumentation Marker and Cap #25826

Witnesses

- "+" E. Rim Gatewell, N30W, 76.15'
- Top Center Fire Hyd., N60W, 75.44'
- "+" N. Rim San. M.H., S30E, 46.89'
- P.K. W. Face MBT Pole, N45E, 31.06'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff  
 Surveyor's Michigan License No. 25826

Date 11-10-93



RECEIVED  
 REGISTERED LAND SURVEYORS  
 NOV 10 1993  
 5:10 PM '93