

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &

REMONUMENTATION

For corners in

<u>WAYNE</u> (County)	Located in: Huron Township	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MAR 17 1998

SECTION

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-1-97 *DOJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on November 7 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-3	1. 1817	G.L.O.	Fletcher	Notes	Post
	2. 1930's	WPA Notes	N/A	Section Map and Ties	Iron
	3. 1973	W.C.R.C.	Coon	Witness Record	1/2" Iron
	4. 1977	Cert. Survey	Arthurs #11358	L. 19813 P. 739	Iron Pipe Stake
	5. 1977	Cert. Survey	Lokey #90347	L. 19878 P. 236-237	N/A
	6. 1981	Unrec. Survey	Pettibone	DECO Survey	3/4" Pipe
	7. 1989	L.C.R.C.	Sandomierski #24616	L. 24145 P. 259	1/2" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found a 1/2" pipe in a hole at the C/L intersection of Sigley Road (asph.) running East and West and Merriman (gravel) running North and South per the following witnesses:

\$4.00 REMONUMENTATION

Center top nut hydrant, M= N11W 94.86', R= 94.95' (7), 95.00' (3): N edge cable route mkr., M= S20E 78.25', R= 78.13' (7): PK E side util pole, M= S31W 67.76', R= 67.83' (4), 67.82' (6): PK NW face util pole, M= S50W 73.53', R= 73.55' (7): Nail w/WCRC tag W face util pole, M= N26W 55.21', R= 55.28' (3 & 4), 55.15' (6).

Measure West to H-3 = 2656.06' (WPA = 2655.69') (G.L.O. = 2640.0') (DECO = 2656.09')  
Measure North to I-2 = 2616.11' (WPA = 2615.46') (G.L.O. = 2640.0')  
Measure East to J-3 = 2658.49' (WPA = 2657.45') (G.L.O. = 2640.0')  
Measure South to I-4 = 2624.90' (WPA = 2625.33') (G.L.O. = 2640.0') (DECO = 2624.99')

RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF  
WAYNE COUNTY, MI  
Receipt #43169

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Replaced an existing 1/2" pipe with a 1/2" x 36" rebar and a 2" diameter aluminum cap stamped "Wayne Co. Remon. #25854." Also set a new monument box.

C/L Top Nut Hydrant N 11° W 94.86'  
Nail w/W.C.R.C. Tag in NW Face Util. Pole N 50° E 46.42'  
\*+ NW Rim San. MH S 63° E 68.93'  
North Edge Cable Route Marker S 20° E 78.25'  
Nail w/W.C.R.C. Tag in W Side Util. Pole S 31° W 68.11'

P.K. Nail in NW Face Util. Pole S 50° W 73.53'  
P.K. Nail in S Face Util. Pole N 68° W 125.31'  
Nail w/W.C.R. Tag in W Face Util. Pole N 26° W 55.23'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/16/97  
Surveyor's Michigan License No. 25854

