

DEC 21 1998

FILE DO NOT MAIL

SURVEY & REMONUMENTATION

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WAYNE (County)	Located in: Huron Township	Corner Code #
1. Public Land Survey	T 4S R 9E	I-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-15-98
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Bruce Antcliff, in a field survey on October 29 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11	Description	Notes	Post
1. 1817	G.L.O.	Fletcher	
2. 1930's	WPA Notes	N/A	Section Map and Ties
3. 1964	H.C.M.A. Survey Map	N/A	N/A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found 1' dia. stone with drill hole on line with old fence line E/W.

\$4.00 REMONUMENTATION
RECORDED
FOREST E. YOUNGLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #101302

\$7.00 DEED

Measure South to I-12 = 2641.80' (WPA = 2642.47', 2641.65' & 2641.94')(G.L.O. = 2640.00')(H.C.M.A. = 2642.70')

Measure West to H-11 = 2638.24' (WPA = 2638.57' & 2639.52')(G.L.O. = 2641.98')(H.C.M.A. = 2639.13')

Measure East to J-11 = 2656.93' = (WPA = 2657.00')(G.L.O. = 2639.34')(H.C.M.A. = 2656.98')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Replaced stone with 4" x 36" concrete monument with a 1/2" rebar and a 2" diameter aluminum cap stamped "Wayne Co. Remon. #25826". (Not in roadway.)

- Set nail w/WCR tag E. side 15" elm, N55°E, 12.70'
- Set nail w/WCR tag N. side 12" ash, S82°E, 25.03'
- Set nail w/WCR tag W. side 8" ash, S04°E, 7.58'
- Set nail w/WCR tag S. side 24" oak, N46°W, 69.50'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-17-98

Surveyor's Michigan License No. 25826

R LCR 7 4R 1PG U DBJ



Liber-30051

Page-749.0

12/21/1998 09:20AM