

FILE DO NOT MAIL
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber-30864 Page-8
99595549 12/30/1999
F.E. Youngblood, Wayne Co. Register of Deeds

Wayne (County)	Located In: Huron Twp.	Corner Code #
1. Public Land Survey	T 4 S R 9 E	J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-8-99
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds St
Number

I, Michael S. Hoben, in a field survey on Sept. 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13	1817 GLO Notes	Preston	N/A	Post
	1920's WPA			Cross
	WCRC			Cross
	1974 WCRC			Mon. in box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 I didn't find any evidence of previous monumentation. I reset with a MAG nail using K-13 and found irons. This point falls on the edge of a farm field and 0.30' S centerline of Will Carlton RD (asph.).

Agrees with the following witnesses:

WCRC 1974
NW Top Stern Hydrant 37.54' (m=37.51')

Distance to K-13 = 2635.59' (GLO = 2640')(WPA = 2634.15')(ET '94 = 2635.59')
Distance to I-13 = 2650.90' (GLO = 2640')(WPA = 2650.50')
(OVER)


FEB 28 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 I set a 1/2" x 18" rebar with a 2" aluminum cap stamped "Wayne County Monument MI Act 345 #35994" in a new monument box. It is not a common corner.

N 14° E	120.03'	SW corner house # 2475
N 77° E	67.93'	Set "+" centerline W'ly and N. headwall
S 60° E	60.61'	Set "+" centerline W'ly end S. headwall
S 9° W	20.22'	FD. PK nail w/ tag #10705 top of guard rail post
N 25° W	43.12'	FD. Nail and WCRC tag E'ly face Util. Pole
N 22° W	37.51'	Centerline top nut hydrant
N 7° E	33.00'	FD. Capped iron (unreadable)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Michael S. Hoben
Surveyor's Michigan License No. 35994

Date Dec. 27, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1999

R LCR 12 4R 2P₉₀ A DOZ

SECTION B:

WCBT witnesses ??

NE 69.75' "X" in N wall (gone)
SE 69.85' "X" in S wall (gone)
SW 82.86' to P.K. nail in DE pole (gone)
NW 35.81 to P.K. nail in MBT pole

Liber-30864 Page-9

WPA witnesses 1930

NE 69.75' "X" in N wall (gone)
SE 69.85' "X" in S wall (gone)
SW 82.86' to P.K. nail in DE pole (gone)
NW 35.81 to P.K. nail in MBT pole

WCRC witnesses 1974

Fd. P.K. nail in cold patch
NE 90.98' to P.K. nail in DE pole
NW 36.74' to P.K. nail in MBT pole

RECEIVED &
FEB 28 2000

SECTION