

MAR 02 1999

Libert-30031

Page-771.0

12/21/1998

09:23AM

DEC 21 1998
FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 SECTION

For corners in

WAYNE (County)	Located in: Huron Township	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-15-98 *DBJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bruce Antcliff, in a field survey on October 29 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1. 1817	G.L.O.	Fletcher	Notes	Post
	2. 1920's	WPA Notes	N/A	Section Map and Ties	Iron
	3. 1979	Cert. Survey #1623	Arthurs	L. 20676 P. 685	I.P. Stake

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found a 1/2" pipe on line of a tree row and fence line running North and South.

Set Nail w/W.C.R. Tag SE Face 14" Ash N 31° E 3.30' (3 = 3.30')
Fnd. P.K. w/Tag (Nothing on it) NE Face 20" Ash S 23° E 7.24' (3 = 7.24')

Note: Arthurs also references a 30" oak to the south at 174' which checks with WPA witnesses of a 20" oak s'ly at 173'.

Measure West to calculated K-11 = 2606.51' (WPA = 2604.83')(G.L.O. = 2640.00')
Measure East to M-11 = 2613.91' (WPA = 2609.66')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Replaced 1/2" pipe with a 4" x 36" concrete monument with a 1/2" rebar and a 2" diameter aluminum cap stamped "Wayne Co. Remon. #25826." (Not in roadway.)

Set Nail w/W.C.R. Tag SE Face 14" Ash N 31° E 3.30'
Fnd. P.K. w/Tag (Nothing on it) NE Face 20" Ash S 23° E 7.24'
Set Nail w/W.C.R. Tag W Face Twin 12" & 20" Ash S 10° W 25.37'
Set Nail w/W.C.R. Tag E Face Utility Pole N 27° W 187.14'



The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-17-98

Surveyor's Michigan License No. 25826

R LCR 7 4R 1PG U D. O. J.