

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 4.00 REMONUMENTATION
 \$ 7.00 DEED
 26 DEC 96 12:43 P.M. RECEI A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER EDS
 WAYNE COUNTY, MI

For corners in

WAYNE
 (County)

Located in: Huron
 Township

Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>4S</u> R <u>9E</u> | <u>M-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

LI 29260 PA 576

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: DEC 17, 1996
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

96526792

I, Randy Kolehouse, in a field survey on December 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-6	1817	G.L.O.	Fletcher	Notes	Post
	1930's	WPA Notes	N/A	Section Map and Ties	Iron
	1973	W.C.R.C.	Coon	Witness Record	1" Iron Pipe
	1974	Cert. Survey	Stanley #12031	L. 18794 P. 358-363	Iron Pipe
	1974	Cert. Survey	Stanley #12031	L. 18968 P. 139-141	Iron Pipe
	1978	L.C.R.C.	Soderberg #17635	L. 20523 P. 755	Conc. Mon. in Box
	1987	Cert. Survey	Crossman #9428	L. 23282 P. 879-881	Conc. Mon. in Box

Records indicate this corner is common with A-6 T4S R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found a concrete monument in a monument box 3' East of the C/L of Inkster Road (asphalt) running North and South that checks one remaining WPA witness and also checks the following witnesses:

WPA Notes (1930's)	L.C.R.C. L. 20523 P. 755 (1978)
D.E. Pole SW 118.05' (m. 118.56')	Nail & Tag in D.E. Pole West 31.71' (m. 31.69')
	P.K. Nail D.E. Pole SE 118.55' (m. 118.56')
W.C.R.C. Witness Record (1973)	E. Edge Asphalt 12.25' (m. 12.3')
Nail NW Face MBT Pole NE 125.68' (m. 125.80')	
Nail SW Face MBT Pole SE 118.00' (m. 118.56')	Cert. Survey L. 23282 P. 879-881 (1987)
NE Corner House SW 103.25' (m. 103.12')	W.C.R.C. Nail & Tag NW Side Util. Pole N 55° E 126.0' (m. 125.80')
Nail N Face D.E. Pole W 31.74' (m. 31.69')	P.K. W Side Util. Pole S 20° E 118.60' (m. 118.56')
	W.C.R.C. Nail & Tag S Side D.E. Pole S 15° W 159.18' (m. 159.16')
	W.C.R.C. Nail & Tag N Side D.E. Pole N 80° W 31.71' (m. 31.69')

Measure North to M-5 = 2617.91' (WPA = 2618.0') (G.L.O. = 2640.0')
 Measure South to M-7 = 2619.85' (WPA = 2619.6') (G.L.O. = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Set brass "Wayne Co. Remon." disk and survey cap #25854 on an existing concrete monument in an existing monument box.	
Nail w/W.C.R.C. Tag in W Side MBT Pole N 17° E 125.80'	Corner of House(?) #21592 S 84° W 103.12'
P.K. Nail in NE Side 12" Poplar S 56° E 61.51'	Nail w/W.C.R.C. Tag in N Side P. Pole N 80° W 31.69'
P.K. Nail in W Side MBT Pole S 09° E 118.56'	Nail w/W.C.R.C. Tag in W Side MBT Pole N 17° E 125.80'
Nail w/W.C.R.C. Tag in E Side P. Pole S 16° W 159.16'	East Edge Asphalt 12.3'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/24/96
 Surveyor's Michigan License No. 25854

