

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

RC 1595

\$ 13.00 MISCELLANEOUS RECORDING
28 DEC 94 9:40 A.M. RECEIPT# 144
RECORDED
INDEXED
WAYNE COUNTY REGISTERED PLAT
WAYNE COUNTY, MI

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located in: Huron Township	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L127800PA662

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *DRJ*
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1595

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	6	5	4	3	2	1				
5											
6	18	17	16	15	14	13	12	11	10	9	8
7											
8	19	18	17	16	15	14	13	12	11	10	9
9											
10	30	29	28	27	26	25	24	23	22	21	20
11											
12	31	30	29	28	27	26	25	24	23	22	21
13											

I, Randy Kolehouse, in a field survey on October 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7	1817	G.L.O. Notes	N/A	Post
	1930's	WPA Notes	N/A	Iron
	1973	WCRC Notes	N/A	1" Iron Pipe - Brought to Top of A.C. w/Bent Boat Spike
	1974	Cert. Survey L. 18794 P. 358 & 360	Stanley	Iron Pipe
	1977	Cert. Survey L. 19884 P. 896 & 897	Crossman	Mon. in Hand Hole
	1978	Cert. Survey L. 20356 P. 817 & 818	Crossman	Mon. in Hand Hole

Last two surveys are for A-7 T4S R10E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 I found 1/2" rebar in 4" dia. concrete monument in monument box at C/L of West Road (gravel/west & asphalt/east) 3' West of C/L Inkster Road (asphalt) running N-S which agrees with the following witnesses.

Cert. Survey L. 18794 P. 360 D.E. Pole SW'ly 39.95' (39.97')	Cert. Surveys in T4S R10E L. 19884 P. 896 & 897 and L. 20356 P. 817 & 818 Both by Same Person S 45° W 40.00' Nail & "WCRC" Cap in Util. Pole (39.97' m) N 50° W 58.66' Top Bolt on Hyd. (58.70' m)
WCRC Nail w/Tag SE Face D.E. Pole SW 40.00' (39.97' m) C/L of Hyd. NW 58.71' (58.70' m)	

Measures N to M-5 = 5237.79' (G.L.O. = 5280') (WPA = 5237.56')
Measures S to M-8 = 2639.19' (G.L.O. = 2640') (WPA = 2639.06' S-24 T4S R9E & 2638.92' S-19 T4S R10E)
(CS L. 19884 P. 896 & L. 20356 P. 817 = 2638.85')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 I set an aluminum cap stamped "Wayne Co. Remon." on existing concrete monument in an existing monument box at the corner.

P.K. SE Face Util. Pole N 37° E 62.55'
P.K. N.E. Face Util. Pole S 23° E 61.12'
Nail w/Tag "WCRC" SE Face Util. Pole S 58° W 39.97'
C/L Top Nut Hyd. N 55° W 58.70'



The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/19/94
Surveyor's Michigan License No. 25854