

APR 25 1995

RC 1597

\$ 13.00 MISCELLANEOUS RECORDING
28 DEC 94 9:40 A.M. RECEIVED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
FOREST & TOPOGRAPHICAL QUALITY CONTROL BOARD
1994

For corners in

<u>WAYNE</u> (County)	Located in: Huron Township	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>9E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L127800PA664

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-7-94
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	4	5	4	3	2	1					
3											
4	7	6	9	10	11	12					
5											
6	10	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Randy Kolehouse, In a field survey on October 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 1817	G.L.O. Notes	N/A	Post
1930's	WPA Notes	N/A	Mon. T4S R9E
1973	WCRC Notes	N/A	Iron Flush w/Top of A.C.
1976	MDSH Witnesses	N/A	Stone T4S R10E
1976	L.C.R.C. L. 19461 P. 704	Hooth	1/2" Pipe in Mon. Box
1977	L.C.R.C. L. 19632 P. 929	Wilderson	Mon. in Road Box
1977	L.C.R.C. L. 20074 P. 309	Arthurs	WCRC Hand Hole Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 I found a concrete monument in monument box in the C/L of Inkster Road (asphalt) running N-S which agrees with the following witnesses. This corner is now common to A-11 T4S R10E. G.L.O. had set A-11 17.82' North of this corner. WPA shows it as being common.

Ties for T4S R9E
L.C.R.C. L. 20074 P. 309
NW 85.77 WCRC Ref. Tag in Util. Pole (85.68' m)
SSE 66.66' WCRC Ref. Tag in Util. Pole (66.48' m)

Ties for T4S R10E
L.C.R.C. L. 19461 P. 704 & MDSH Notes
P. Pole N 16° W 85.74' (85.68' m)

WCRC
Nail w/Tag Bell Pole SE 66.70' (66.48' m)
Nail w/Tag D.E. Pole NW 85.77' (85.68' m)

L.C.R.C. L. 19632 P. 929
N 15° W 85.75' WCRC Cap E. Side P. Pole (85.68' m)

Measures North to M-9 = 5268.41' (G.L.O. = 5280')(WPA = 5267.66' T4S R9E - 5267.30' T4S R10E)
Measures South to M-13 = 5311.39' (G.L.O. = 5280')(WPA = 5312.05' T4S R9E - 5311.37' T4S R10E)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 I set an aluminum cap stamped "Wayne Co. Remon." on existing concrete monument in an existing monument box.

P.K. w/Tag "WCRC" W Face Util. Pole S 15° E 66.48'
NE Cor. Hse. #27016 S 59° W 93.95'
NE Cor. Hse. #27004 N 69° W 90.00'
Nail w/Tag "WCRC" NE Face Util. Pole N 12W 85.68'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/14/94
Surveyor's Michigan License No. 25854

