

SURVEY & REMONUMENTATION

RC 1598

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING
 28 DEC 94 9:40 A.M. RECEIVED
 COUNTY CLERK
 REGISTER OF DEEDS

For corners in

| | | |
|---------------------------------------|--------------------------------------|------------------------------|
| <u>WAYNE</u> (County) | Located in: <u>Huron</u> Township | Corner Code # <u>M-13</u> |
| 1. Public Land Survey | T <u>4S</u> R <u>9E</u> | <u>M-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

L127800PA665
 Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 12-7-94 *RJ*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

RC 1598

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|
| 2 | 0 | 5 | 4 | 3 | 2 | 1 | | | | | |
| 3 | | | | | | | | | | | |
| 4 | 7 | 0 | 9 | 10 | 11 | 12 | | | | | |
| 5 | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | |
| 7 | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | |
| 9 | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | |
| 11 | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | |

I, Randy Kolehouse, in a field survey on July 28 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|------|--------|--------------|-----|----------------------------|
| M-13 | 1817 | G.L.O. Notes | N/A | Post |
| | 1930's | WPA Notes | N/A | Cross on Brass Rod T4S R9E |
| | 1973 | WCRC Notes | N/A | Iron T4S R10E |
| | | | | Monument in Box |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 I found 1/4" rebar in concrete in monument box in the C/L of Will Carleton Road (concrete) running E-W. No witnesses remain. Checks closely to WPA measurements to L-13 & M-11.

WCRC

Nail w/Tag D.E. Pole SE 70.42' (70.00' m)

Measures West to L-13 = 2624.70' (G.L.O. = 2640') (WPA = 2624.01')
 Measures North to M-11 = 5311.39' (G.L.O. = 5280') (WPA = 5312.05' T4S R9E & 5311.37' T4S R10E)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 I set an aluminum cap stamped "Wayne Co. Remon." on existing concrete monument in an existing monument box.

- Nail in Top of Guard Rail Post at W Side Driveway N 30° E 18.59'
- P.K. in Top of Guard Rail Post at E Side Driveway N 57° E 35.82'
- Nail w/Tag "WCRC" NE Face Lt. Pole S 59° E 70.00'
- P.K. E Face Util. Pole N 17° W 33.78'



The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/14/94
 Surveyor's Michigan License No. 25854