

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|                                       |                                    |               |
|---------------------------------------|------------------------------------|---------------|
| <u>WAYNE</u><br>(County)              | Located in: Brownstown<br>Township | Corner Code # |
| 1. Public Land Survey                 | T <u>4S</u> R <u>10E</u>           | <u>B-5</u>    |
|                                       | T _____ R _____                    | _____         |
|                                       | T _____ R _____                    | _____         |
|                                       | T _____ R _____                    | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____            | _____         |
|                                       | S _____ T _____ R _____            | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____            | _____         |
|                                       | S _____ T _____ R _____            | _____         |

**LI29360PA580**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: DEC 17, 1996  
**WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE**  
 Register of Deeds Stamp & File Number

96326795

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on November 27 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  | •  |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

| B-5 | 1817   | G.L.O.       | Fletcher       | Notes                | Post      |
|-----|--------|--------------|----------------|----------------------|-----------|
|     | 1930's | WPA Notes    | N/A            | Section Map and Ties | Iron      |
|     | 1959   | Legg Sub.    | Lokey          | L. 84 P. 33          | N/A       |
|     | 1973   | W.C.R.C.     | Coon           | Witness Record       | Iron      |
|     | 1979   | Cert. Survey | Arthurs #11358 | L. 20518 P. 87-89    | Iron Pipe |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 Found two 1/2" pipes side by side in the C/L of King Road (gravel) running East and West (used West pipe) on the approximate easterly line of the Penn Central Railroad right-of-way.

W.C.R.C. Witness Record (1973)  
 Top Hyd. NE 55.22 (m. 59.22')  
 AT&T Pole SW 50.42 (m. 47.05')  
 "+" SE Bolt RR Signal NW 45.29' (m. 45.75')  
 Cert. Survey L. 20518 P. 87-89 (1979)  
 Nail in West Side Util. Pole SSW 28.31' (m. 28.40')  
 Nail in SE Side Util. Pole SW 47.08' (m. 47.05')

\$ 4.00 REMONUMENTATION  
 \$ 7.00 DEED  
 26 DEC 96 12:43 P.M. RECEI A  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER EDS  
 WAYNE COUNTY, MI


Measure West to A-5 2676.35' (WPA = 2676.1') (G.L.O. = 2653.2') (Survey L. 20518 P. 87 = 2676.24')  
 Measure East to C-5 2706.93' (WPA = 2706.1') (G.L.O. = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 Replaced an existing 1/2" pipe with a 1/2" rebar, brass "Wayne Co. Remon." disk and survey cap #25854.

Top Nut of Hydrant N 45° E 59.22'  
 Nail w/W.C.R.C. Tag in E Face Util. Pole South 28.40'  
 Nail w/Washer SE Face S 65° W 47.05'  
 Nail w/W.C.R.C. Tag in NW Face Util Pole S 65° W 47.23'  
 "+" SE Bolt RR Signal Base N 63° W 45.75'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Signed by Randy J. Kolehouse Date 12/24/96  
 Surveyor's Michigan License No. 25854