

**SURVEY &  
REMONUMENTATION**

**RC 1599**

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**COMMISSION**

For corners in

WAYNE  
(County)

Located in: Brownstown Corner Code #  
Township

- |                                       |                                     |
|---------------------------------------|-------------------------------------|
| 1. Public Land Survey                 | T <u>4S</u> R <u>10E</u> <u>C-5</u> |
|                                       | T _____ R _____                     |
|                                       | T _____ R _____                     |
|                                       | T _____ R _____                     |
| 2. Property Controlling<br>In Section | S _____ T _____ R _____             |
|                                       | S _____ T _____ R _____             |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____             |
|                                       | S _____ T _____ R _____             |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on October 25 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-5	1817	G.L.O. Notes	N/A	Post
	1930's	WPA Notes	N/A	Iron
	1973	WCRC Notes	N/A	1" Iron Pipe ± 1' Below Gravel
	1975	Cert. Survey L. 19211 P. 220	Stanley	N/A

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-5 I found 1/2" rebar at C/L of King & Beech Daly Roads (gravel). All recorded witnesses are gone.

**WCRC Notes**

Nail w/Tag D.E. Lt. Pole N'16 30.83' (30.96' m)

Measures East to D-5 = 2573.8' (G.L.O. = 2633.40') (WPA = 2573.71' S-8 - WPA = 2573.61' S-17)

Measures South to C-7 = 5227.04' (G.L.O. = 5280') (WPA = 5226.78' S-17 - WPA = 5225.29' S-18)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-5 Replaced 1/2" rebar with 4" x 36" concrete monument with aluminum cap stamped "Wayne Co. Remon."

Nail w/Tag "WCR" W Face 20" Oak S 20° E 95.70'

"+" NE Rim San. M.H. S 40° W 40.69'

"+" SE Rim G.V. & W. N 52° W 93.26'

Nail w/Tag "WCRC" W Face Util. Pole N 02° W 30.96'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/14/94  
Surveyor's Michigan License No. 25854

1127800PA666  
\$ 13.00 MISCELLANEOUS RECORDING  
28 DEC 94 9:41 A.M. RECEIVED 16  
RECORDED  
FORRELL C. HUNTER, REGISTRAR OF DEEDS  
WAYNE COUNTY, MI

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-7-94 *DPJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

