

**SURVEY & REMONUMENTATION**

APR 25 1995

**RC 1613**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located in: City of <u>Trenton</u>	Corner Code # <u>M-9</u>
1. Public Land Survey	T <u>4S</u> R <u>10E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**L127800PA680**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-7-94 *[Signature]*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

**RC 1613**

I, Randy Kolehouse, in a field survey on October 24 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	16	17	18	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

M-9	1817	G.L.O. Notes	N/A	Post
	1930's	WPA Notes	N/A	Monument
	1983	L.C.R.C. L. 21944 P. 551 RC #829	Young	Iron Rod in Mon. Box

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-9 I found 1/2" rebar in monument box at C/L of Van Horn Road (concrete) running E-W, 10' West C/L Division Street (concrete) running South, which agrees with the following witnesses.

- L.C.R.C. RC #829
- North 26.87' Nail E Face Lt. Pole
- N 40° E 53.53' Nail E Face Guy Pole
- S 55° E 59.84' Top Operating Nut on Hyd.
- S 10° W 34.15' Nail West Face D.E. Co. Pole

\$ 13.00 MISCELLANEOUS RECORDING  
28 DEC 94 9:42 A.M. RECEIPT# 168  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

- Measures East to C/L Jefferson = 371.20' (WPA = 370.91')
- Measures West to C/L = 2588.78' (G.L.O. = 2615.58') (WPA = 2589.07')
- Measures South to M-11 = 5215.12' (G.L.O. = 5280') (WPA = 5215.74')

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-9 Set aluminum cap stamped "Wayne Co. Remon." on existing 1/2" rebar in an existing monument box.

- Nail E Face Util. Pole North 26.80'
- Nail SE Face Util. Pole N 40° E 53.52'
- C/L Top Nut Hyd. S 58° E 60.00'
- Nail W Face Util. Pole S 15° W 34.25'



The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/14/94  
Surveyor's Michigan License No. 25854