

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WEXFORD
 (County)

Located In: Corner Code -//

- | | | | | | |
|------------------------------------|---|-----|---|----|-------------|
| 1. Public Land Survey | T | 21N | R | 9W | |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous | S | 7 | T | R | NE COR 6L-5 |
| Property in Sec. | S | 7 | T | R | NW COR 6L-5 |

*filed
8/17/89
8700*

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	•	•										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **C.F. ROSE**, in a field survey on **OCTOBER 14**, 19 **85**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NE COR 6L5

NE COR 6L5

NW COR 6L5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NE COR 6L5

FD. 1 1/2"x 15" SQ. WOOD, POINTED STAKE BOTTOM IN NET SOIL FOR MEANDER POST, ON N. LINE OF SEC. 7, NEAR WEST EDGE OF LAKE CADILLAC (EDGE OF WATER IS 7'± EAST); PER D.E. TEED SURVEY DATED AUG. 11, 1924. FILE CARD 21-68, SUNNYSIDE PARK; NOTES ON FILE AT GOURDIE FRASER & ASSOC., TRAVERSE CITY. TEED NOTES CALL FOR IR. 5' WEST; THIS IS NOW

NE COR 6L5

(CONT.)
 GONE. NOTE, THIS M.C. IS ALSO REFERRED TO AS THE N.E. CORNER OF GOVT. LOT 5 IN DESCRIPTION'S IN THIS AREA.

NW COR 6L5

FD. 1" PIPE, NEAR E. SHORE OF LAKE MITCHELL, ON NORTH LINE OF SEC. 7 (NW COR. GOVT. LOT 5), WEXFORD CO., FOR MEANDER CORNER PER 1946 SUB'N. PLAT BY TEED OF "MITCHELL-HATCH PLAT". CORNER FALLS DIRECTLY UNDER 5' HIGH, E-W, CHAIN LINK FENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

NE COR 6L5

FD. 1 1/2"x 15" SQ. WOOD, POINTED, STAKE BOTTOM. REPLACED W/5/8"x 3/4" REROD W/L.S. CAP.
 9" W. BIRCH S28°W 23.23'
 8" MAPLE S62°W 14.65'
 8" MAPLE N82°W 20.31'
 6" MAPLE N12°W 24.20'
 FD. ROUND CONC.
 MON. S06°13'18"E 250.27'

NE COR 6L5

NW COR 6L5

FD. 1" PIPE.
 FD. SQ. CONC.
 MON. S89°23'E 78.17'
 20" W. PINE N62°E 85.50'
 P. POLE S03°E 47.92'
 EDGE OF LAKE WEST 60'±
 W. END OF 5' HIGH, CHAIN LINK FN. WEST 32'±

Signed by Carl F. Roser 12028 3-30-89 Date

Surveyor's Michigan License No. _____

