

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
 WEXFORD

(County)

Located In:

Corner Code //

- |                                    |     |            |           |
|------------------------------------|-----|------------|-----------|
| 1. Public Land Survey              |     | T 21N R 9W | A-1, A-2  |
|                                    |     | T R        |           |
|                                    |     | T R        |           |
|                                    |     | T R        |           |
| 2. Property Controlling in Section | S   | T R        |           |
|                                    | S   | T R        |           |
| 3. Miscellaneous Property in Sec   | S 6 | T R        | MC-1413.2 |
|                                    | S   | T R        | S. of A-2 |

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat  
 5. Private Claims

I, CARL T. KIISKILA, in a field survey on DECEMBER 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration**

A-1	A-2	MC
NO EVIDENCE OF G.L.C. CORNER, BUT 15' LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.C. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW		

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

A-1	A-2	MC
FD. RECORDED IN MON BOX FOR NW COR 5-6. IRON FITS 1907/30 SURVEY BY D.E. TEEB, 1881, P. 07 AND 1966 DEPT. SURVEY BY K.J. OSTLING, R.S. #10068; BOTH SURVEYS IN 5-6. P. 07, MONUMENTING RECORDED A MON BOX IN 1972, WE COULD NOT FIND ANY OF HIS 3-WITTS TO VERIFY THIS POSITION.	FD 3/4" PIPE FOR NW 1/4 COR 5-6. PIPE FITS D.E. TEEB 1907/30 SURVEY OF 5-6 AND 1966 DEPT. SURVEY BY K.J. OSTLING OF NW 1/4 5 & 6. CTR. OF MON IS 130' W. WEST.	FD OLD RUSTY 2" PIPE FOR M.C. ON WEST LINE OF 5-6 AT NE LY. EDGE OF LAKE MITCHELL. N.E. LY. EDGE OF LAKE IS 75' W. 21' SOUTH.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

A-1	A-2	MC
FD. 5/8" RECORDED IN MON BOX IN CTR. OF E-W B. TOP ROAD. #11" MAPLE N35°E 69.40' #10" MAPLE S85°W 59.51' NO COR HOUSE S40°W 28.8' #POWER POLE S50°W 41.20' FD 4" AT POST S15°E 29.2'	FD 3/4" PIPE, ADDED 5/8" 17" RECORDED W/PS CAP, SET CEDAR POST W/LOC. TAG. 5" W. PINE N25°W 6.50' 4" MAPLE N53°E 17.96' 3" W. PINE S48°E 8.89' #15" MAPLE S50°W 4.68'	FD OLD RUSTY 2" PIPE. #14" W. PINE N46°E 6.2' #26" R.OAK N18°W 34' FD 5/8" RECORDED (NW COR. 50VT. LOT 4) N06°09'20"W 21.11'

# BY OTHERS

# R.S. #10068 1966 MIT.

# A.D. TEEB 1907 WIT.

Signed by

*Carl T. Kiiskila*

Date

5-23-96

Surveyor's Michigan License No.

33981

