

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
 SECTION

(County)	Located In:	Corner Code //
1. Public Land Survey	T 214 R 9W	B 1, B-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 6 T R	8
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, **CARL T. KIISKILA**, in a field survey on **DECEMBER, 1**, 19 **94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

NO EVIDENCE OF S.W. CORNER, S. LINES, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE S.W. CORNER LINE AGREE; UNLESS NOTED BY ITEM "B" BELOW

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

<b>B-1</b>	<b>B-2</b>	<b>B</b>
FO 1/2" IRON IN APPROX. CTR OF E-W B. TOP ROAD FOR THE NW 1/4 COR. S-6. IRON FITS 1907/08 SURVEY IN S-6 BY D.E. TEEB, RECORDED LI. 1, Pg. 07 AND 1965 DEPT. SURVEY BY K.J. OSTLING, RLS #10060, IN NW 1/4 OF S-6. OLD FN. TO SOUTH IS 29' +/- WEST.	FO 1" PIPE FOR CTR. OF S-6. PIPE FITS SURVEYS OF S-6 BY A.J. TEEB IN 1896/1908; D.E. TEEB IN 1907 (BOTH RECORDED IN LI. 1, Pg. 6 & 7) AND BY RLS, K.J. OSTLING IN 1966 DEPT. SURVEY OF NW 1/4 OF S-6. PIPE IS AT ROTTED OF LEGAL CORNER POST, FOX FARM FENCE REMAINS TO N & W.	FO OLD 1" PIPE AT S-E LY. EDGE OF DRAINAGE CANAL TO WEST AND NORTH, FOR NW COR. OF NE 1/4 OF SW 1/4 S-6. PIPE FITS TWO D.E. TEEB W. PINE WIT. REMAINS OF 1908. PIPE IS IN OLD E-W FOX FARM FENCE REMAINS.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

<b>S-1</b>	<b>B-2</b>	<b>B</b>
FO 1/2" IRON ROD. #14" TAMARACK S60°E 43.60' 10" R. OAK S75°W 54.25' #18" TRI. R. OAK S60°W 24.02' SEE 4" x 4" POST WITH LOCATION TAG SOUTH 33'	FO 1" GALVANIZED PIPE. #2" MAPLE S60°W 17.80' 4" W. PINE N75°W 24.77' 4" MAPLE N35°W 16.74' 4" W. MAPLE N10°E 22.51'	DRIVE 3/8" x 3/4" ROPED INSIDE OF FO. OLD 1" PIPE. 8" MAPLE S10°W 1.4' 12" W. PINE N72°E 21.2' 7" TW. MAPLE S62°E 12.4'



\*= PS, M. McCLEUNG, 1972 WIT.  
 \*\*= WIT. BY OTHERS      \*\*= RLS, K. OSTLING 1966 WIT.

Signed by *Carl T. Kiiskila*  
 Surveyor's Michigan License No. 21981

Date *5-23-96*