

MAR 8 1 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 10:33

Linda Loughmiller  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

WEXFORD (County)

Located In: Corner Code --#

- 1. Public Land Survey      T1N    9W      B-13  
                                   T      R  
                                   T      R  
                                   T      R
- 2. Property Controlling    S      T      R  
    in Section                S      T      R
- 3. Miscellaneous          S      T      R  
    Property in Sec.        S      T      R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, CRAIG J. PULLEN, in a field survey on DECEMBER 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-13 1837 GLO SURVEY BY J. BRINK, WOOD POST TAMARACK 10" N57°E 16 LKS TAMARACK 11" N70°W 13 LKS
- 1892 D.E. TEED SURVEY, STAKE & BOTH GOVERNMENT WITNESSES OK
- 1963 C. ROSER, PS# 12028 SURVEY FOR MSHD, CORNER RECORDED IN L.2, P.874, SET 3/4" PIPE BY SINGLE PROPORTION MEASURE 11" MAPLE DUE N 62.83' 9" ELM S87°E 28.97' 21" TWIN MAPLE S42°E 45.14' NW CORNER SEC.6, T20N, R9W N89°10'58"E 236.41'
- 1991 C. ROSER SURVEY, CORNER RECORDED IN L.4, P.98, SET 1" PIPE WITH DNR CAP FROM 1963 WITNESSES. NO EVIDENCE OF 1963 MSHD PIPE. SET CEDAR POST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-13 FOUND DNR CAP ON 1" PIPE, CEDAR POST, AND WITNESSES FROM L.4, P.98 INTACT. THIS CORNER IS ACCEPTED AS A FAITHFUL AND CAREFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: December 28, 1993  
Richard D. Wilcox  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-13 S 1/4 CORNER, SEC.31, T21N, R9W
- 1" X 8' GALVANIZED PIPE WITH DNR CAP
- 15" MAPLE DUE NORTH 62.83' (1963 WIT.)
- 4" BALSAM N55°E 21.46'
- 15" TWIN MAPLE S45°E 45.14' (1963 WIT.)
- 5" BALSAM S60°W 8.22'
- NE CORNER, SEC.1, T20N, R10W N89°11'E 236.4'



Signed by Craig J. Pullen

Date DECEMBER 23, 1993

Surveyor's Michigan License No. 39095