

MAR 8 1 1994

COMMISSION

RECEIVED

1993 DEC 29 AM 10: 33

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in
WEXFORD

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 21N R 9W C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

CRAIG J. PULLEN in a field survey on DECEMBER 16, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at row 13, column C.

A. Description of original monument and accessories and/or subsequent restoration:

- C-13 1837 GLO SURVEY BY J. BRINK, WOOD POST CEDAR 10" N68 1/2 E 9 LKS HEMLOCK 10" N70 W 18 LKS
1892 D.E. TEED SURVEY, STAKE AND 2 WITNESSES OK
1963 C. ROSER, PS# 12028 SURVEY FOR MSHD, CORNER RECORDED IN L.2, P.876, SET 1 1/2" PIPE FROM EVIDENCE TO NORTH N70 W 18" ELM 22.90' N25 E 4" ELM 43.00' N89 12 33 E RR TRACKS 149.10' S89 12 33 W N 1/4 COR., SEC.6, T20N, R9W 65.87'
1991 C. ROSER SURVEY, CORNER RECORDED IN L.4, P.98, FOUND 1 1/2" PIPE FROM 1963 SURVEY DROVE 1" X 8' GALVANIZED PIPE UNDERNEATH FOUND 1 1/2" X 30" PIPE AND SET CEDAR POST WITH LOCATION TAG

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-13 FOUND 1 1/2" PIPE AND CEDAR POST AND ALL WITNESSES FROM L.4, P.98 INTACT EXCEPT 3" ELM. SET 5/8" X 36" IRON WITH BRASS CAP INSIDE OF EXISTING 1 1/2" PIPE. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved
Date: December 28, 1993
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13 SE CORNER, SECTION 31, T21N, R9W
5/8" X 36" IRON WITH BRASS CAP STAMPED:
SC. 31, 32, 1993, CJP 39095
GALVANIZED FENCE POST DUE SOUTH 5.0'
GALVANIZED FENCE POST DUE NORTH 16.20'
4" ELM DUE WEST 31.03'
CENTER OF RAILROAD TRACKS EAST 149.1'
N 1/4 CORNER SECTION 6, T20N, R9W WEST 65.87'



Signed by Craig J. Pullen
Surveyor's Michigan License No. 39095

Date DECEMBER 28, 1993