

SURVEY &
REMONUMENTATION

APR 16 1999

RECEIVED

1998 DEC 30 AM 10:18

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

<u>WEXFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>9W</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, CRAIG J. PULLEN, PS, in a field survey on OCTOBER 7, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13 1838 WOOD POST BY J. BRINK HEMLOCK 10" N8½°E 17' HEMLOCK 7" N20°W 11'
1994 C. PULLEN, PS #39095, SURVEY IN SECTION 6, T20N, R9W, SET 5/8" X 36" IRON WITH BRASS CAP EQUIDISTANT FROM THE SW CORNER SECTION 32 AND SE CORNER SECTION 32, T21N, R9W, AND ON THE LINE EXTENDED FROM THE SW CORNER SECTION 32, T21N, R9W, AND THE NE CORNER SECTION 6, T20N, R9W. N27°W 12" COTTON WOOD 23.79', N64°E 6" WHITE BIRCH 42.00', S88°54'W NE CORNER SECTION 6, T20N, R9W 28.83', S18°W ROAD SIGN 34.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 FOUND 5/8" IRON & BRASS CAP 2' NORTH OF CENTERLINE OF EAST 52 ROAD AND 30' EAST OF CENTERLINE OF 170TH AVENUE AND 4 PREVIOUS WITNESSES. DISTANCE TO THE SW CORNER OF SECTION 32 IS 2639.75' AND THE DISTANCE TO THE SE CORNER OF SECTION 32 IS 2639.76'. OSCEOLA CORNER IS 28.83' WEST. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 SOUTH 1/4 CORNER OF SECTION 32, T21N, R9W
5/8" X 36" IRON & BRASS CAP STAMPED: CJP, 1998, 39095, 1/4, 32
N27°W 12" COTTON WOOD 23.79'
N64°E 6" WHITE BIRCH 42.00'
S88°54'W NE CORNER SECTION 6, T20N, R9W 28.83'
S18°W ROAD SIGN 34.30'
S60°W 10" RED PINE 73.88'



Signed by Craig J. Pullen Date NOVEMBER 6, 1998
Surveyor's Michigan License No. 39095

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

Peer Group Reviewed and Approved

Date: 130 Oct 98
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

LIGER 05 PAGE 95