

MAR 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC -2 PM 3: 51

RECEIVED

For corners in
WEXFORD

(County)

Located In:

Corner Code #

1. Public Land Survey	T	21N	R	9W	E-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CRAIG J. PULLEN, in a field survey on OCTOBER 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 1837 GLO SURVEY BY J. BRINK, WOOD POST SUGAR 12" N7°W 29L BIRCH 13" N65°E 48L
 1890 A.J. TEED SURVEY, FOUND REMAINS OF OLD WITNESSES AND STAKE, PUT IN NEW STAKE STONES, JUGS & CROCKERY.
 1898 D.E. TEED SURVEY, STAKE 59L (38.94') EAST OF OSCEOLA COR.
 DATE UNKNOWN FROM WEXFORD COUNTY ROAD COMMISSION WITNESSES TEL. POLE N19°E 38L POPLAR NE 79.30' SCHOOL PORCH CONC. COR. SW 88.30' 2665.4' WEST OF US-131

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 FOUND WELL PT. 2.0' BELOW ROAD SURFACE IN CENTERLINE OF E-W ROAD AND CENTERLINE OF ROAD TO NORTH. FOUND 1" PIPE 38.94' WEST OF WELL POINT AND IN LINE WITH FENCE TO SOUTH AND IT IS 88.30' NE OF CONC. PORCH WITNESS FROM ROAD COMM. WITNESSES, ACCEPTED AS THE N¼ COR. SEC.5, T20N, R9W, AND RAISED WITH ½" IRON AND CAP. DISTANCE BETWEEN THE OSCEOLA CORNER AND WEXFORD CORNER MATCHES D.E. TEED'S FROM 1898. ACCEPTED WELL POINT AS SE CORNER SEC.32, T21N, R9W, AND RAISED WITH 5/8" X 36" IRON WITH BRASS CAP STAMPED: SC, 32, 33, CJP 39095, 1993. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 SE CORNER OF SECTION 32, T21N, R9W
 5/8" X 36" IRON WITH BRASS CAP OVER WELL POINT
 N72°E POWER POLE 94.06'
 S62°E POWER POLE 62.44'
 S53°W 14" MAPLE 51.43'
 WEST N¼ COR. SEC.5, T20N, R9W
 (½" IRON AND CAP) 38.94'



Peer Group Reviewed and Approved
Date: Nov. 29, 1993
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by Craig J. Pullen
Surveyor's Michigan License No. 39095

Date NOVEMBER 23, 1993