

MAY 10 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>WEXFORD COUNTY</u>	Located in:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>09W</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1999 DEC - 1 PM 3:05  
 REGISTER OF DEEDS  
 WEXFORD COUNTY, MI  
*Richard D. Wilcox*

RECEIVED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, George D. Smith, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-4) 1848 GLO subdivision by Orson Lyon D.S. 7" Hemlock-S67½E-13, 10" Beech-N60W-18.
- 1886 A. Teed Survey, Liber 1, Page 16. 30" W. Pine-N28W-59, 24" W. Pine-S55E-61.
- 1906 D. Teed pointed stone, stake N57½W 40' in line with C&M slab burner (pointed stone replaced with wood stake 1916).
- 1909 A. Teed Liber 1, Page 14, pointed stone.
- 1973 J. Granger, PS #16041, LCRC Liber 1, Page 280. Found iron in monument box MSHD R.O.W. Posts East 75.00' and 86.00'. Powerpole-S70W-98.38', Powerpole-S80E-114.24'.

A continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-4) Found 3/4" square steel bar with rounded top 0.50 west of centerline US-131 in monument box. This corner is accepted as the best available evidence of the position of the original corner being the quarter corner common to Sections 9 and 10, T21N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-4) Set Wexford County brass cap stamped 9, 10 1999 PS #39098 on 3/4" bar.
- S86W 151.09 Powerpole
- S33W 136.83 Powerpole
- S77E 112.26 Powerpole
- S56E 100.37 "X" on northwest corner of concrete base of light pole



LIBER 05 PAGE 175

Peer Group Reviewed and Approved  
 Date: 12 Nov 99  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

Signed by *George D. Smith*  
 Surveyor's Michigan License No. 39098

Date: 11-12-99

A continued:

- G-4) 1978 J. Wilcox, PS #14102, LCRC Liber 3, Page 178. Found iron in monument box, witnesses same as 1973 LCRC Liber 1, Page 280.
- 1978 Fletcher, PS #19830. Certificate of Survey, Liber 1, Page 637. Witnesses same as 1973 LCRC Liber 1, Page 280.
- 1980 MSHD Government monument witness recorded by J. Carlson. Found 1 1/2" iron in monument box, S80W-98.66'-power pole, S75E-114.03'-power pole, East-0.63'-small ple nail.
- 1980 J. Wilcox, PS #14102. Certificate of Survey Liber 1, Page 827. Found iron in monument box, witnesses same as 1973 LCRC Liber 1, Page 280.
- 1990 Carlson PS #24589 LCRC Liber 4, Page 70. Found 1 1/2" iron in monument box. Power pole-S81W-100.86', easterly leg of sign-N31E-82.11', power pole-S76E-113.42', center line of first light pole north of drive-S26E-179.22'.
- 1991 D. Schripsema, PS #24617. Certificate of Survey, Liber 70, Page 891. Found iron in monument box witnesses same as 1973 LCRC, Liber 1, Page 280.
- 1995 J. Ray, PS # 25869. Certificate of Survey, Liber 76, Page 95. Found iron in monument box, witnesses same as 1973 LCRC Liber 1, Page 280.
- 1995 J. D. Geers, PS #33977. Certificate of Survey, Liber 74, Page 616. Found iron in monument box, witnesses same as 1973 LCRC recorded in Liber 1, Page 280.