

SURVEY & REMONUMENTATION

MAY 10 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

| | | |
|------------------------------------|-----------------------------|---------------|
| <u>WEXFORD COUNTY</u> | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>21</u> N R <u>09</u> W | <u>G-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED
 1999 DEC - 1 PM 3:06
Julia Thompson
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, George D. Smith, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-7) 1848 GLO subdivision by Orson Lyon D.S. Maple-N57W-26, 7" Beech-N24½E-21.
- 1880 A.J. Teed, Liber 1, Page 25. Corner found no description given. 30" W. Pine-N34E-31.
- 1887 Fuller, Liber 1, Page 35. Corner found no witnesses or description given.
- 1907 D. Teed, Liber 1, Page 26 reset from old witness, 30" W. Pine-N34E-31 links, 30 "W. Pine-N4W-73, 24" W. Pine-N56W-72½.
- 1908 Cavanagh, Liber 1, Page 37. Corner found no description or witnesses given.
- 1981 Plat of Harmony Hills #3. Liber 7, Page 353-355 by F. Finnerty PS #16038. Corner found no description or witness given.
- 1979 Wilcox PS #14102 LCRC, Liber 3, Page 214. Found 5/8" iron replaced with Wexford County monument. N21W-36.26'-10" R. Pine, N15E-29.59'-20" R. Pine, N60E-28.36'-8" R. Pine.
- 1979 Wilcox PS #14102. Certificate of Survey, Liber 1, Page 771. Found 5/8" iron, witnesses same as 1979.
- 1992 Finnerty PS #16038 Certificate of Survey, Liber 71, Page 975. Found Wexford County monument, no witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-7) Found Wexford County Monument and three witnesses from 1979 Wilcox, PS #14102 LCRC. This corner is accepted as the best available evidence of the position of the original corner being the section corner common to Sections 16, 15, 21, 22, T21N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-7) Wexford County Monument stamped 16, 15, 21, 22, 1999, PS #39098

| | | |
|------|-------|-----------------------------------|
| N59E | 28.42 | 14" Red pine (1979 Wilcox 28.36') |
| N16E | 29.62 | 22" Red pine (1979 Wilcox 29.59') |
| N13W | 36.34 | 18" Red pine (1979 Wilcox 36.26') |
| S41W | 13.85 | 16" Cherry |



Peer Group Reviewed and Approved
 Date: 12 Nov 99
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

Signed by _____
 Surveyor's Michigan License No. _____

Date 11-12-99

LIBER 05 PAGE 160