

**SURVEY & REMONUMENTATION**

MAY 10 2000

RECEIVED

1999 DEC -3 PM 12: 43

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Linda Longmiller*  
WEXFORD COUNTY, MI  
REGISTERED CLERK

For corners in

WEXFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>9W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CRAIG J. PULLEN, PS, in a field survey on OCTOBER 4, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5				4		3		2	1
3													
4	7			8				9		10		11	12
5													
6	18			17				16		15		14	13
7													
8	19			20				21		22		23	24
9													
10	30			29				28		27		26	25
11													
12	31			32				33		34		35	36
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-9 1848 G.L.O. RESURVEY BY O. LYON, WOOD POST, BEECH 10 S29E 16, SUGAR 9 N59 1/2E 10
- 1897 A. J. TEED SURVEY IN SECTION 27 FOUND OLD STAKE, BEECH 10 S35E 30 1/2, SUGAR 10 S2 3/4E 54 3/4
- 1908 CAVANAGH SURVEY IN SECTION 22 NO WITNESSES, CORNER SHOWN AS IN.
- 1988 GRANGER ENGINEERING SURVEY IN SECTION 27 BY JAMES A. RAY PS#25869 L.C.R.C. LIBER 4, PAGE 4. SET 1/2" IRON & CAP BY S. P. N05°W POWER POLE 52.28', S05°W 32" COTTONWOOD STUMP 41.15', ALSO 1991 SURVEY IN SECTION 22, SAME WITNESSES
- 1994 J. DEAN GEERS PS#33977 L.C.R.C. LIBER 4, PAGE 221 FD. 1/2" IRON 1' SOUTH OF CENTERLINE OF ROAD OPPOSITE FENCE TO NORTH. SET 5/8" X 36" IRON IN MON BOX. S45°W 44.57' SET IRON, S40°E 42.10' SET IRON, N03°W 33.63' TOP OF SE COR. OF STEEL CORNER FENCE POST, N03°W 52.24' POWER POLE (FOUND SPIKE)
- 1998 WADE-TRIM SURVEY IN SECTION 27 BY CRAIG J. PULLEN PS#39095 LIBER 77, PAGE 682 FD. 5/8" IRON IN MON BOX 0.5' N CENTERLINE 48 RD., N83°W P. POLE 177.49', N08°W P. POLE 52.41' N07°W TOP CNT. STEEL FE. POST 33.87', N78°E P. POLE 263.01'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-9 FD. 5/8" IRON IN MON. BOX 0.5' NORTH OF CENTERLINE 48 ROAD AND 4 PREVIOUS WITNESSES. CORNER IS 4' EAST OF FENCE LINE TO NORTH. ADDED WEXFORD COUNTY MONUMENT BRASS CAP. THIS CORNER IS ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- H-9 1/4 CORNER COMMON TO SECTION 22 & 27, T21N, R9W
- 5/8" X 36" IRON & BRASS CAP
- N3°W 60 NAIL IN P. POLE 52.42'
- N3°W TOP STEEL FENCE POST 33.63'
- S40°E FOUND 1/2" IRON 42.11'
- S45°W FOUND 1/2" IRON 44.77'



Peer Group Reviewed and Approved  
Date: 12 Nov 99  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

Signed by Craig J. Pullen

Date November 5, 1999

Surveyor's Michigan License No. 39095

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

LREP 05 PAIF 190

REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995