

MAY 10 2000

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>WEXFORD COUNTY</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>09W</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECEIVED**  
 1999 DEC - 1 PM 3:05  
*Richard D. Wilcox*  
 WEXFORD COUNTY, MI  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, George D. Smith, P.S., in a field survey on June 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**


- I-7) 1848 Orson Lyon, D.S. Sugar Tree 20" in diameter for corner.  
8" Beech-S63 1/2 E-22, 6" Beech-S8W-18.
- 1894 A.J. Teed, Liber 1, Page 24, reset by running 1/2 mile north and south. 10" Beech-N27W-87L.
- 1896 A.J. Teed, Liber 1, Page 23, corner found no description or witnesses given.
- 1902 D. Teed, Liber 1, Page 39, found cedar stake from witness. 10" Beech-N27W-87L, Elm-N26E-34.
- 1981 Wilcox Associates survey records Field Book 150, Page 58. Found monument box, no witnesses given.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- I-7) Found 3/4" pipe in monument box, replaced with 5/8"x36" iron with brass cap stamped: 15, 14, 22, 23 1999 PS #39098. This corner is accepted as the best available evidence of the position of the original corner being the section corner common to Sections 15, 14, 22, 23, T21N, R9W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- I-7) Wexford County brass cap stamped 15, 16, 22, 23, 1999 PS #39098.
- S75E 122.61 4" Maple
- S16W 163.04 Powerpole
- N80W 60.64 14" Elm
- N76W 62.98 14" Elm



Peer Group Reviewed and Approved

Date: 12 Nov 99  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

T15FR

05 PAGE 156

Signed by *George D. Smith*  
 Surveyor's Michigan License No. 39098

Date 11-12-99