

SURVEY & REMONUMENTATION

MAY 10 2000

RECEIVED

1999 DEC -3 PM 12: 43

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

WEXFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 9W	I-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, CRAIG J. PULLEN, PS, in a field survey on JUNE 10, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-10 1848 G.L.O. RESURVEY BY O. LYON, WOOD POST, SUGAR TREE 20 N4W 19, BEECH 7 S71E 17
- 1897 A. J. TEED SURVEY IN SECTION 27, SET ON LINE AT 1/2 DISTANCE. NO WITNESSES
- 1903 D. E. TEED SURVEY IN SECTION 26, FOUND IRON ELM 8 N65E 75, ELM 10 N34 1/2 E 84 1/2
- 1965 CO. WITNESS BOOK, PP S20°E 57.80', 30" ELM N30°E 49.30', 20" ELM N75°E 48.50'
- 1972 WILCOX & ERICKSON SURVEY BY JERRY L. WILCOX PS#14102 IN SECTION 26, L.248, P.910, L.C.R.C. L.1, P.107, 1/2" BAR IN MONUMENT BOX & CL BIT., N50°W T. POLE 36.92', N30°E 28" ELM STUMP 56.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-10 FOUND 5/8" IRON IN MONUMENT BOX, 0.5' WEST OF CENTERLINE 45 ROAD & 8' NORTH OF CENTERLINE 48 1/2 ROAD AND ONE 1972 WITNESS. ADDED WEXFORD COUNTY BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-10 1/4 CORNER COMMON TO SECTIONS 26 & 27, T21N, R9W
- 5/8"X36" IRON & BRASS CAP STAMPED: 1999, CJP, 39095, 1/4, 26, 27
- N27°E 9" APPLE 123.52'
- N60°E SW CORNER SHED FOUNDATION 195.60'
- N58°W POWER POLE 37.42'
- S9°W POWER POLE 216.45'



Peer Group Reviewed and Approved

Date: 12 Nov 99

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by Craig J. Pullen

Date November 5, 1999

Surveyor's Michigan License No. 39095