

SURVEY & REMONUMENTATION

MAY 10 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>WEXFORD COUNTY</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>21</u> N R <u>09</u> W	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard D. Wilcox
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

1999 DEC -1 PM 3:06

RECEIVED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5										●			
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

I, George D. Smith, P.S., in a field survey on June 21, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-5) 1848 GLO subdivision by Orson Lyon, D.S. 3" Spruce-N85 1/2 E-63, 6" Tamarack- S28W-59.
- 1896 A. Teed, Liber 1, Page 18. Corner found 5" Tamarack-N59W-25 1/2 feet.
- 1902 D. Teed, Liber 1, Page 23. Corner found no description or witnesses given.
- 1981 McClung PS #13037 LCRC Liber 3, Page 317, Liber 3, Page 247. Set Wexford County monument on line and equal distance. 10" Maple-N30E-17.00', 3" Spruce-S80E-7.30', 8" Tamarack-S30E-8.00'.
- 1992 J. Ray, PS #25869 Certificate of Survey, Liber 75, Page 373. Found Wexford County monument, N30E-10" Maple-17.00', S80E-6" B. Spruce-7.64', S30E-10" Tamarack-8.40', N25W-6" S. Maple-26.28'.
- 1996 C. Pullen, PS #39095 Certificate of Survey, Liber 75, Page 951. Found Wexford County Monument witnesses same as 1992 Ray PS # 25869 Certificate of Survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-5) Found Wexford County Monument and two witnesses from McClung PS #13037 LCRC and two from 1992 Ray PS #25869 Certificate of Survey. Corner falls 1.78 feet west of calculated M.O.L. position, held position of monument as corner position. This corner is accepted as a careful and faithful re-establishment of the position of the original corner, being the quarter corner common to Sections 11 and 14, T21N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-5) Wexford County monument stamped PS #39098 1999 11/14.
- S29E 8.35' 10" Tamarack (1981 McClung 8.00', 1992 Ray 8.40')
- S69E 7.60' 5" Tamarack
- N48W 10.68' 5" Tamarack
- N30E 16.84' 6" Twin Maple (1981 McClung 17.00', 1992 Ray 17.00')



LIBER 05 PAGE 162

Peer Group Reviewed and Approved

Date: 12 Nov 99
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

Signed by _____
 Surveyor's Michigan License No. 39098

Date 11-12-99