

**SURVEY &
REMONUMENTATION**

MAY 10 2000

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>WEXFORD COUNTY</u>	Located In:	Corner Code #
1. Public Land Survey	<u>T 21N R 09W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard D. Wilcox
 WEXFORD COUNTY, MI
 REGISTERED SURVEYOR

RECEIVED
 1999 DEC - 1 PM 3: 06

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, George D. Smith, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-3) 1848 GLO subdivision by Orson Lyon, D.S. 12" Beech-S23E-17, 20" Norway Pine-N31 1/2 E-29.
- 1897 A.J. Teed Survey Liber 1, Page 18 corner found. Pine-N31 1/2 E-29 (Government tree), 14" N. Pine-S72W-22 1/2'.
- 1974 J.L. Wilcox Associates survey records field book 27, Page 23. Found 1 1/2" pipe 1' north of old fence remains west, and in line with old fence north-south. 6" Maple-West-27.04', 16" Pine-S25W-28.45', 3" Maple-N10E-21.69'.
- 1977 J. Switalski, PS #13045 Certificate of Survey, Liber 1, Page 557. Found Wexford County Monument N72E-22.95'- 6" Maple, S17E-21.14'-18" Y. Pine, N17E-29.40'-5" Maple.
- 1981 McClung PS #13037 LCRC Liber 3, Page 317, Liber 3, Page 247. Found Wexford County Monument, 8" Maple-S85W-27.00', 20" N. Pine-S35E-21.75', 4" Maple-N10E-29.46'.
- 1984 McClung PS #13037 Certificate of Survey, Liber 2, Page 34. Found Wexford County Monument witnesses same as 1981 LCRC, Liber 3, Page 247 and 318.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-3) Found Wexford County Monument and one witness from 1897 Teed Survey and one witness from 1974 Wilcox Associates survey records, this corner is accepted as a careful and faithful perpetuation of the position of the original corner being the section corner common to Sections 2, 1, 11, 12, T21N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-3) Wexford County Monument stamped 2, 1, 11, 12 1999 PS #39098

S89W	26.80	8" Maple (27.04 Wilcox Associates records)
S73W	22.25	15" Stump (14" N. Pine S72W, 22.5' Teed)
N55W	27.44	8" R. Pine
N51E	47.32	10" R. Pine
S04W	36.62	8" Poplar

Peer Group Reviewed and Approved

Date: 12 Nov 99
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor



LIBER 05-160

Signed by _____
 Surveyor's Michigan License No. _____

Date 11-12-99