

**SURVEY & REMONUMENTATION**

MAY 10 2000

RECEIVED

1999 DEC -3 PM 12: 44

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Linda Laughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

<u>WEXFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>9W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, CRAIG J. PULLEN, PS, in a field survey on AUGUST 13, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-8 1848 G.L.O. RESURVEY BY O. LYON, WOOD POST, BEECH 20 S42E 13, HEMLOCK 18 N39W 17
- 1883 A. J. TEED SURVEY IN SECTION 23 NO WITNESSES.
- 1960 COUNTY ROAD COMMISSION WITNESS BOOK STEEL FENCE POST, 15" MAPLE EAST 100.00', TELEPHONE PEDESTAL N50°W 41.30', FENCE POST WEST 31.25', FENCE POST EAST 31.20'
- 1997 GEORGE SMITH PS#39098 L.C.R.C. L.5, P.15 FOUND HEX BOLT, SET MONUMENT BOX CENTERLINE 47 ROAD. N46°E 45.84' 6" POPLAR, N41°E 49.75' FENCE POST, N14°W 77.66' 10" ELM, N25°W 80.45' 8" POPLAR, N85°W 65.05' 4" MAPLE

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- K-8 FOUND HEX BOLT INSIDE OF STEEL SIGN POST IN MONUMENT BOX 0.3' EAST OF CENTERLINE OF 47 ROAD AND IN LINE WITH FENCE AND TREE LINE EAST, WEST OLD FENCE WEST. FOUND ROAD COMMISSION MAPLE TO EAST. REPLACED WITH 5/8"X36" IRON AND BRASS CAP INSIDE OF STEEL POST. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-6 1/4 CORNER COMMON TO SECTIONS 23 & 24, T21N, R9W
- 5/8"X36" IRON & BRASS CAP STAMPED: CJP, 39095, 1999, 1/4, 23, 24
- N36°E FENCE POST 49.75'
- N41°E 6" POPLAR 45.80'
- N89°W 6" MAPLE 65.13'
- N28°W 7" POPLAR 80.38'
- N18°W 14" ELM 78.12'



Peer Group Reviewed and Approved

Date: 12 Nov 99  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

Signed by Craig J. Pullen Date October 21, 1999  
Surveyor's Michigan License No. 39095