

MAY 10 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1999 DEC -3 PM 12: 44

Linda Doughmiller
WEXFORD COUNTY, MI
REGISTERED CLERK

For corners in

WEXFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>9W</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CRAIG J. PULLEN, PS, in a field survey on AUGUST 13, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-9 1848 G.L.O. RESURVEY BY O. LYON, WOOD POST, SUGAR 13 S28E 12, SUGAR 8 N73E 16
- 1883 A. J. TEED SURVEY IN SECTION 23 SET FROM ONE WITNESS, PUT IN STONE AND STAKE. HEMLOCK 36 S70W 62L
- 1898 A. J. TEED SURVEY IN SECTION 25 FOUND STAKE FROM MY OLD WITNESS. EAST TREE OF 3 SUGARS 6", N301/2E 90L
- UNDATED COUNTY ROAD COMMISSION WITNESS BOOK 1" PIPE R.E.A. POLE N45°W 45.50', T.P. S25°W 64.32', TELEPHONE PEDESTAL N10°W 136.50', TELEPHONE PEDESTAL SW 71.54'
- 1982 GRANGER ENGINEERING SURVEY BY JAMES A. RAY PS#25869 L.1, P.934 1/2" IRON 3' SOUTH OF CENTERLINE E-W ROAD, N45°E 90.9' POWER POLE, S25°W 73.3' POWER POLE, S65°W 90.62' 12" APPLE
- 1993 WILCOX SURVEY BY J. DEAN GEERS PS#33977 L.72, P.392 FOUND SPIKE OVER MONUMENT, S28°W 72.72' TELEPHONE RISER, S49°W 80.40' FENCE POST, N52°E 90.90' POWER POLE, N17°E 101.02' WOOD POST, S18°E 55.23' STOP SIGN POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-9 FOUND 5/8" IRON IN MON BOX IN CENTERLINE OF 48 ROAD & 1' WEST OF 47 ROAD. ADDED BRASS CAP. AREA FILLED FOR 48 ROAD RECONSTRUCTION IN 1993. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-8 SECTION CORNER COMMON TO SECTIONS 23, 24, 25 & 26, T21N, R9W
- 5/8"X36" IRON & BRASS CAP STAMPED: CJP, 39095, 1999, 23, 24, 25, 26
- N50°E POWER POLE 89.02'
- S18°W CORNER FENCE POST 118.62'
- S79°W CORNER FENCE POST 159.82'
- N64°W POWER POLE 147.28'



Peer Group Reviewed and Approved
Date: 12 Nov 99
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by *Craig J. Pullen* Date October 21, 1999
Surveyor's Michigan License No. 39095

REC'D 05 PM 20:3