

**SURVEY &
REMONUMENTATION**

MAY 10 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>WEXFORD COUNTY</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>09W</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 1999 DEC -1 PM 3:05
Richard D. Wilcox
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

I, George D. Smith, P.S., in a field survey on June 23, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-5) 1848 GLO subdivision by Orson Lyon D.S. 7" Sugar-N16¼E-11, 13" Lynn-Southeast-16.
- 1889 A. Teed, Liber 1, Page 21, Stake and 1 witness okay.
- 1907 D. Teed, Liber 1, Page 19, found stake, 30" W. Pine-S04W-112, 4" W. Pine-S67½W-24½, Greenstone North 100 links.
- 1976 J. Erickson, PS #16929 LCRC, Liber 2, Page 791. Set Wexford County Monument straight line and ½ way between northeast and northwest corner, S80W-12" Elm-50.23', due north 20" Walnut 100.04'.
- 1977 J. Switalski, PS #13045 Certificate of Survey, Liber 1, Page 557. Found Wexford County Monument
- 1978 J.L. Wilcox PS #14102 Certificate of Survey, Liber 1, Page 607, found Wexford County Monument S80W-12" Elm-50.23', North 20" Walnut 100.40'.
- 1986 J. Ray, PS #25869 Certificate of Survey, Liber 2, Page 226, found Wexford County Monument witnesses same as 1978 Wilcox, PS #14102 Certificate of Survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- L-5) Found Wexford County monument set by J. Erickson, PS #16929, Liber 1, Page 791, 5' east of fence to South and in line with fence to East. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the quarter corner common to Sections 12 and 13, T21N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5) Wexford County monument stamped PS #39098 1999, 12/13.
- S89W 48.76 18" Maple
- N85W 134.64 18" Twin Basswood
- S67W 116.06 Powerpole
- S88E 117.25 6" Cherry
- West 5.0 5/8" iron (removed)

Peer Group Reviewed and Approved

Date: 12 Nov 99
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor



LIBER **05 PAGE 155**

Signed by [Signature]
 Surveyor's Michigan License No. 39098

Date 11-12-99