

RECORDED & INDEXED  
FELONY

MAR 31 1994

COMMISSION

RECEIVED

1993 DEC 29 AM 9:39

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wexford  
(County)

Located In:

Corner Code #

- 1. Public Land Survey                    T 21N R 9W                    M-2  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous                        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.                        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-2) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Hemlock 8" S 39° W 51, Beech 12" N 57 1/2° W 40.
- M-2) 1882 Teed survey in Section 1: Beech okay, Hemlock is a Maple 8" 2' East of Hemlock 10"
- M-2) 1967 DNR (Roser) survey in Section 1: 10" Norway Pine, S 66° W 75.92 6" Norway Pine, S 55° E 55.19 6" Norway Pine, N 87° E 56.85 5" Norway Pine, N 26° W 35.47 old North-South fence post - East 18', centerline of North-South trail - West 9'.
- M-2) Liber 1, page 931, Erickson survey in Section 1: 2" pipe 2' East of road edge, due East 12" Pine 56.90, N 35° W 12" pine 35.50, S 70° W 12" Pine 75.90
- M-2) 1982 Erickson survey Liber 2 page 66, survey in Section 1: 2" Pipe on East edge of road, 12' dirt trail, N 35° W 12" Pine 56.9 N 35° W 10" Pine, 35.41, N 75° W 10" Pine 48.02, N 45° E 7" Pine 45.70, S 60° E 8" Pine 15.22
- M-2) 1986 Ray survey, 2" pipe 2' East, 7" Pine 45.70, S 60° E 8" Pine 15.22

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A. (con't)

- M-2) 1989 Ray survey, 1/2" Iron, N 35° W 12" Pine 35.41, N 75° W 10" Pine 48.02, N 45° E 7" Pine 45.70, S 60 E 8" Pine 15.22

B.

- M-2) 1/4 Section corner common to Sections 1 and 6, T21N, R8W  
 Found 1/2" Iron ±2' West of East edge of road and ±6' East of centerline of a North-South road and ±80 West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.


Peer Group Reviewed and Approved

Date: 11/29/93

*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-2) Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: E 1/4, PS 33989, 1993  
           N 28° W - 35.61 - 12" Red Pine  
           N 68° W - 48.16 - 10" Red Pine  
           S 65° W - 75.98 - 14" Red Pine  
           N 28° W - 35.61 - 8" Red Pine



Signed by *Richard D. Wilcox*

Date 11/29/93

Surveyor's Michigan License No. 33989