

REGISTERED & RECORDED

MAR 3 1 1991

COMMISSION

RECEIVED

LAND CORNER RECORDATION CERTIFICATE 1993 DEC 29 AM 9:40  
Filing Requirement of Act 74, Mich. P.A. 1970

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

Wexford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21</u> N R <u>9</u> W	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-3) 1838 GLO Section post by John Brink, Deputy Surveyor, Maple 12" S 48 1/2° W 32, Y. Pine 18" N 76° W 23.
- M-3) 1853 GLO Section post: "Y" Pine 23" N 19 3/4° E 31, Beech 15" S 19° E 27, survey of T21N, R8W
- M-3) 1967 DNR survey in Section 1: 2" pipe (1" deep) MDSH 1967, S 55° W 46.75 5" N. Pine, West 39.40 Corner fence post, S 30° W 54.57 8" Twin N. Pine.
- M-3) 1975 Wilcox survey in Section 7: Found 2" pipe, S 55° W 46.75 5" Norway Pine, West 39.40 fence corner, S 30° W 54.57 8" Twin N. Pine.
- M-3) 1977 Switalski survey in Section 12: 2" pipe, N 35° E 62.80 7" Jack Pine, S 15° E 52.88 3" Maple, S 60° E 62.48 6" Y. Pine, S 80° W 64.24 7" Y. Pine.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- M-3) Section corner common to Sections 1 and 12  
Found bent 1/2" rerod over 2" pipe. Pulled rerod. Pipe is ±4' East of centerline of North-South road and ±15' South of centerline of private drive to East and ±3' South of fence line to West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11/29/93  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3) Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: SE, 1, PS 33989, 1993  
N 41° E - 62.90 - 8" Jack Pine  
S 12° E - 53.10 - 5" Maple in clump  
S 79° W - 70.90 - 8" Red Pine  
N 74° W - 62.03 - 10" Poplar



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989