

RECORDED

MAR 31 1994

COMMISSION

RECEIVED

1993 DEC 29 AM 9:40

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wexford
(County)

Located In:

Corner Code #

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

- 1. Public Land Survey T 21N R 9W M-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard Wilcox, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-4) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Beech 8" N 72 1/2° W 25, Beech 7" S 53 1/4° W 18.
- M-4) 1883 Bradly survey in Section 12: Hemlock (forked) 30 N 13 1/4° W 12 links
- M-4) 1907 Teed survey in Section 12: White Pine 20" N 61° W, 71, White Pine 16" S 62° W 74, White Pine 30" S 31° E 8; found Bradley's witnesses badly rotten & burnt and remains of stake also found some bodies witnesses 30" White Pine Southeast, no notes for it.
- M-4) 1977 Switalski survey in Section 12: Set Wexford Co. monument, N 15° W 84.73 8" Maple, N 73° E 104.47 30" Maple, S 25° E 24.44 6" Maple (Liber 1, page 557)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-4) 1/4 Quarter corner common to Sections 12 and 17, T21N, R8W
Found Wexford County monument 45.5' East of North-South fence and ±178' West of centerline of trail. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11/29/93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4) Found Wexford County monument, left in place
N 73° E - 104.47 - 30" Maple
N 69° W - 55.95 - Face of blaze on 30" Pine stump
N 38° E - 59.21 - 3" Oak
S 24° E - 24.40 - 6" Maple in clump
N 12° W - 85.61 - 10" Maple (twin)



Signed by Richard D. Wilcox
Surveyor's Michigan License No. 33989

Date 11/29/93