

RECEIVED

MAR 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 1993 DEC 29 AM 9:40
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 21N R 9W Corner Code M-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-5) 1838 GLO Section corner by John Brink, Deputy Surveyor, Sugar 14" S 47° W 20, Beech 10" N 9- 1/2° W 14.
- M-5) 1853 GLO Section corner by John Brink, Deputy Surveyor, Beech 12" N 43° E 41, Beech 10" S 69 1/2° E, 25, survey of T21N, R8W
- M-5) 1889 Teed survey in Section 13: Stake and witnesses okay.
- M-5) 1973 Erickson survey in Section 13: 1/2" Iron rod, N 40° E - 35.79 - 3" Cherry, S 85° W - 36.23 - 3" Poplar, S 50° W - 40.62 - Power pole (Liber 02, page 791)
- M-5) 1977 Switalski survey in Section 12: 1/2" Iron, witnesses (Liber 2, page 791)
- M-5) 1992 Wilcox survey in Section 13: S 59° W - 40.59 - Power pole, S 79° W - 32.16 - Corner fence post, N 62° W - 34.59 - Fence post, N 32° W - 53.97 - Fence post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5) Section corner common to Sections 12 and 13, T21N, R8W
Found Iron & cap ±2' North of centerline of road to East and 7' North of fence to the West and ±7' East of centerline of a North-South road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.


Peer Group Reviewed and Approved

Date: 11-29-93

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5) Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: SE, 12, PS 33989, 1993
S 59° W - 40.59 - Power pole
S 79° W - 32.16 - Corner fence post
N 35° W - 38.98 - Top center 16" CMP culvert
N 30° E - 35.69 - Top center 16" CMP culvert



Signed by Richard D. Wilcox
Surveyor's Michigan License No. 33989

Date 11/29/93