

CURTIS
REMOVAL

MAR 31 1994

COMMISSION

RECEIVED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 29 AM 9:40

For corners in

Wexford
(County)

Located In:

Corner Code ≠≠

Linda Doughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

- 1. Public Land Survey T 21N R 9W M-6
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-6) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, Sugar 9" S 21° W 8, Beech 14" N 36° W 32.
- M-6) 1889 Teed survey in Section 13: Stake & witnesses okay.
- M-6) 1901 Teed survey in Section 13: Hemlock 14 N 51° E 82, Sugar 2" N 10 1/4° E 121 1/2, Cedar post (B.P.) N 44° W 68
- M-6) 1976 Erickson survey in Section 13: Found old Iron 4' East of centerline (Liber 2, page 791) S 75° E - 36.40 - Power pole, East - 28.28 - 6" Oak, N 20° E - 64.00 - 24" Maple
- M-6) From Wade-Trim records (undated): East Iron - 33', N 28° E - 24" Maple - 63.98, S 59° E - Power pole - 37.90, S 45° W - 8" Locust - 71.58

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-6) 1/4 Section corner common to Sections 13 and 18, T21N, R8W
Found 3/4" iron 4' East of centerline of a North-South road and in centerline of a road to the West. Witnesses from Liber 2, page 791 are good. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6) Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: E 1/4, 13, PS 33989, 1993
East - 33.00 - 1/2" Iron & cap
N 28° E - 63.98 - 24" Maple
S 59° E - 37.90 - Power Pole
S 45° W - 71.58 - 8" Locust
N 42° W - 47.18 - Corner fence post



Signed by *Richard D. Wilcox* Date 11/29/93

Surveyor's Michigan License No. 33989