

SURVEYOR  
REMOVED

MAR 31 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 9:40

For corners in  
Wexford  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 21N R 9W M-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Linda Laughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1838 GLO Section corner by John Brink, Deputy Surveyor, Sugar 11° S 9 1/2° W 50 links, Hemlock 18° N 48° W 22 links
- M-7) 1853 GLO Section corner by John Brink, Deputy Surveyor, Hemlock 20 N 23 3/4° E 30, Sugar 10 S 60 1/2° E 22, survey of T21N, R8W
- M-7) 1889 Teed survey in Section 13: Fence post 42 links West & 4 links South, fence post 42 links West and 44 links North.
- M-7) 1891 Teed survey in Section 13: Found old stake and both witnesses okay, put in RR iron and stones (Richardson's corner is 3 1/2' Southeast)
- M-7) 1901 Teed survey in Section 13: Fence post 42 links West & 45 links South, fence post 42 links West & 44 links North. Iron stake.
- M-7) 1973 Erickson survey in Section 13: N 60° E - 66.65' - Power pole, N 30° W - 47.33' - Power pole
- M-7) From Wade-Trim records (undated): 3/8" iron, N 50° E - fence post 54.54, N 30° W - Power pole 47.62, S 84° W - Yield sign 35.68, S 75° E - Missaukee Co. sign 65.91.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-7) Section corner common to Sections 13, 24, T21N, R9W and Sections 18 and 19, T21N, R8W  
Found 3/8" iron with grader blade ±3' West of centerline of a North-South road and 6' South of centerline of a East-West road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93  
Richard D. Wilcox  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-7) Set 5/8" x 36" iron with Wexford Co. brass cap stamped: SE, 13, PS 33989, 1993  
N 50° E - 54.54 - Fence post  
S 51° E - 46.44 - Fence post  
N 30° W - 47.62 - Power Pole  
S 84° W - 35.68 - Yield Sign  
S 75° E - 65.91 - Miss. Co. sign



Signed by Richard D. Wilcox  
Surveyor's Michigan License No. 33989

Date 11/29/93