

MAR 31 1994

RECEIVED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 29 AM 9:40

For corners in

COMMISSION

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

<u>Wexford</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>9W</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Richard Wilcox, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1838 GLO Section corner by John Brink, Deputy Surveyor, Beech 8° S 67° W 20, Beech 10° N 08° W 20
- M-9) 1853 GLO survey (T21N, R8W), Sugar 13 S 6 3/4° E 22, Sugar 10 N 47 1/2° E 48
- M-9) 1898 Teed survey in Section 24: Sugar 5" (small notch) N 44° W 43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9) Section corner common to Sections 24, 25, 19 and 20, T21N, R8W
Found 1/2" rod in monument box in the centerline of a North-South road and ±2.5' South of the centerline of a East-West road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group Reviewed and Approved

Date: 11-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9) Set 5/8" x 36" Iron with Wexford Co. brass cap stamped: SE, 24, PS 33989, 1993
S 66° W - 78.75 - Top center of phone riser
N 08° W - 161.68 - 4" Cherry
S 84° W - 231.53 - Power Pole
S 10° E - 62.33 - Top of SW corner of curb & gutter in SW quad. of intersection
N 56° E - 59.39 - Power pole

Signed by Richard D. Wilcox Date 11/29/93
Surveyor's Michigan License No. 33989

