

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 21 N.R. 10W


Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 35-36 on south boundary of township.

CORNER MONUMENT Set 1" pipe with ^{4"}aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/31/61

WITNESSES TO CORNER.....



7" Cedar - N 66½ E - 22.3 feet

8" Cedar - N 6½ W - 36.2 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division Land Surveyor during corner search in this area. Found large squared post at corner as established by County Surveyor Sours, date unknown, probably in early 1900's. Both his new bearing trees of record alive and standing. Best available evidence of corner. County survey records explain Sours procedure in establishing this corner.

SURVEYOR'S SEAL

SIGNED *Lance J. Ostling* DATE 11/14/61
REGISTERED LAND SURVEYOR