

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WEXFORD
(County)

Located In: _____ Corner Code ~~##~~

- | | | |
|---------------------------------------|-----------------------------|-------------------|
| 1. Public Land Survey | T <u>21N</u> R <u>10W</u> | <u>K-11, L-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>36</u> T _____ R _____ | <u>12</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, CARL F. ROSER, in a field survey on 2-28, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-11	L-12	12
------	------	----

B. Description of corner evidence found*and/or method applied in restoring or reestablishing corner:

K-11	L-12	12
FB DEPT MON AT NW COR 9-36 AS SET IN 1961 DEPT SRUVEY AT FD SQ CED POST & 1-1/4" PIPE. PIPE ESTABLISHED BY CO. SURVEYOR SOURS IN EARLY 1900'S. COR IS AT NW EDGE TRAIL RD (TRAIL RUNS NE-SW).	ESTABLISHED CTR SEC 36 AT INTERSECTION OF 1/4 LINES.	ESTABLISHED SW COR OF NW1/4-SE1/4 OF 9-36 PER STANDARD BLM INSTRUCTIONS. CTR OF WINDING N-S TRAIL IS 300 1/2 WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11	L-12	12
FB DEPT MON. #30° W PINE STP 658°W 92.6' #30° W PINE STP 639°E 19.2' 16" MAPLE (CLP) 676°W 19.3' 7" MAPLE 686°E 28.9' 6" OAK 638°E 44.6'	DROVE 5/8"x 34" RE-ROD W/RLS CAP; SET CED POST W/LOC TAG. 5" CEDAR N45°W 32.4' 6" MAPLE W/3" MAPLE N40°E 14.7' 6" CEDAR S45°E 26.1' 32" W PINE S05°W 10.3'	DROVE 5/8"x 34" RE-ROD W/LS CAP & SET CEDAR POST W/LOC TAG. 10" MAPLE N18°E 18.9' 12" MAPLE S10°E 18.5' 14" HEM S52°W 13.9' 9" MAPLE N56°W 28.5'

*= 1961 DEPT MITS.

Signed by Carl F. Roser 03-16-91 Date _____
 Surveyor's Michigan License No. 12028

