

MAR 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

RECEIVED

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>21N</u> N. S., R. <u>10W</u> E. W.	<u>D-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

1993 DEC -2 PM 3:50

Richard D. Wilcox
WEXFORD COUNTY, MI
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CRAIG J. PULLEN do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on SEPTEMBER 17 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 1837 GLO SURVEY BY JOHN BRINK
MONU. W. PINE 28
- 1917 SURVEY OF SEC.6, T20N, R10W, BY FRANK MCCLUNG, OSCEOLA CO. SURVEYOR
MONU. NONE MENTIONED. SHOWS A TICK MARK ON SECTION 6 DRAWING 392' W OF THE NE COR. SEC.6.
- 1990 SURVEY BY P. LEEMON #31595, LIBER 4, PAGE 59
MONU. SET 6"X60" CONC. MONU. WITH BRASS CAP.
R. OAK 14" NORTH 214.46 FT.
R. PINE 10" N60°E 39.21 FT.
TRI. B. CHERRY 12X12X10 S74°W 60.27 FT.
R. PINE 10" N63°W 7.68 FT.
FIBERGLASS POST EAST 1.32 FT.
WOVEN FN. E-W SOUTH 64.3 FT.
QUARTZ STONE 3X2.7X1.1 S9°W 46.48 FT.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-13 LEEMON COMPUTED THE LOCATION FOR THIS CORNER USING RECOVERED GLO CORNERS EAST AND WEST. FROM THIS COMPUTED LOCATION ALL IDENTIFIABLE. W. PINE REMAINS WERE TIED INTO HIS TRAVERSE. THE W. PINE STP. MOST CLOSELY FITTING THE CALCULATED LOCATION WAS ACCEPTED BY LEEMON AS THE S¼ OF 32. A POSITION 392' WEST OF THE RECOVERED NE CORNER OF SECTION 6 BY MCCLUNG FITS LEEMON'S E-W PROPORTIONING BUT FALLS ON THE OLD E-W FN. LINE, 64 FT. SOUTH OF LEEMON'S POSITION. IT ALSO FITS THE GLO CALLS ALONG THE TOWNSHIP LINE, GOING WEST FROM THIS CORNER. UPON EXCAVATING THIS LOCATION, THE REMAINS OF A 2" DIAM. WOOD STAKE SURROUNDED BY STONES WAS FOUND TO BE 393.23 FT. WEST OF THE NE CORNER OF SECTION 6. ALL FENCE POSTS ALONG THE FENCE LINE WERE 6 TO 8 INCHES IN DIAM. THIS IS NOT A FENCE POST. THIS LOCATION IS ALSO SUPPORTED BY THE REMAINS OF A CEDAR STAKE AND 8X10X10 STONE, 2638.85 FT. TO THE WEST BEING THE SW OF 32, T21N, R10W. BASED UPON THE RECOVERED EVIDENCE JUST MENTIONED, I FEEL MCCLUNG PERPETUATED THIS LOCATION AND THE SW OF 32 DURING HIS 1917 SURVEY OF SECTION 6. I HAVE REVIEWED THIS EVIDENCE WITH LEEMON AND HE CONCURS, THE 2" DIAM. WOOD STAKE WITH STONE REPRESENTS THE S¼ OF 32. THIS LOCATION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13 S¼ COR. SEC.32, T21N, R10W
SET 6"X60" CONC. MON. WITH U.S.F.S. BRASS CAP
- N55°W 12" RED PINE 48.00'
- N3°W 12" RED PINE 27.29'
- S53°E 8" RED PINE 28.26'
- S42°W 6" RED PINE 36.98'

Peer Group Reviewed and Approved

Date: 12-29-93
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor


SIGNED BY Craig J. Pullen DATE 12-1-93

SURVEYOR'S MICHIGAN REGISTRATION NO. 39095

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Patricia R. Yerman DATE 11/22/93
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. 31595