

SURVEYOR  
MONUMENT

MAR 3 1 1994

COMMISSION

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>21N</u> N. S., R. <u>10W</u> E. W.		<u>F-13</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**RECEIVED**  
 1993 DEC -2 PM 3:51  
*Linda Doughmiller*  
 WEXFORD COUNTY, MI  
 REGISTER OF DEEDS  
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CRAIG J. PULLEN do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on SEPTEMBER 17 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-13 1837 ORIGINAL GOVERNMENT SURVEY BY JOHN BRINK. CEDAR 16" N29°W 12L CEDAR 14" N54°E 32L
- 1990 SURVEY BY P. LEEMON, PS #31595, CORNER RECORDED IN L.4, P.59. SET 2" X 30" STAINLESS STEEL PIPE WITH BRASS CAP HEMLOCK 8" N15°E 16.62' R. MAPLE 10" N73°E 29.13' BALSAM FIR 4" S8°E 38.14' TW. R. MAPLE 8X5 S50°W 2.07' FIBERGLASS POST EAST 1.40'


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-13 LEEMON SET THIS CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE S¼ 32 AND THE SW 34. AFTER REVIEWING THE S¼ OF 32 WITH HIM AND SUBSEQUENTLY NOT USING IT, THIS LOCATION THEN BECAME INVALID. AFTER A CAREFUL SEARCH FOR EVIDENCE OF THE ORIGINAL CORNER AND ITS ACCESSORIES, I FOUND WHAT I BELIEVE TO BE THE REMAINS OF THE GLO CEDAR N29°W 12 LKS. I THEN RECOVERED THIS CORNER UTILIZING THE RECORD BEARING AND DISTANCE, AND SET A 2" X 30" GALVANIZED STEEL PIPE AND BRASS CAP IN THIS POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13 S¼ COR., SEC.33, T21N, R10W SET 2" X 30" GALVANIZED STEEL PIPE & U.S.F.S BRASS CAP
- N83°E 6" CEDAR 37.86'
- S30°W 10" CEDAR 10.93'
- N55°W 12" CEDAR 33.27'
- N6°W 10" RED MAPLE 18.77'

Peer Group Reviewed and Approved  
 Date: 11-29-93  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor



SIGNED BY Craig J. Pullen DATE 12-7-93

SURVEYOR'S MICHIGAN REGISTRATION NO. 39095

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Richard D. Wilcox DATE 11/22/93  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 31595